

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☐

GAS
WELL ☒

OTHER

SINGLE
ZONE ☒

MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR

P. O. Box 749, Denver, Colorado 80201-0749

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

1980' FNL, 1800' FWL (SE1/4NW1/4) Section 12, T10S, R20E

At proposed prod. zone

Same As Above

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately Eight (8) Miles South/Southeast of Ouray, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

1800'

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

2100'±

16. NO. OF ACRES IN LEASE

320

19. PROPOSED DEPTH

6150' WSTC

17. NO. OF ACRES ASSIGNED
TO THIS WELL

80

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5053' GR

22. APPROX. DATE WORK WILL START*

September 10, 1991

23.

(ALL NEW)

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" K-55	24.0#	0- 250'	180 sx Circ. to Surface *
7-7/8"	5-1/2" K-55	17.0#	0-6150'	545 sx Cinc. to Surface *

* Cement volumes may change due to hole size.
Calculate from Caliper log.

EIGHT-POINT RESOURCE PROTECTION PLAN ATTACHED.

DIVISION OF
OIL GAS & MINING

I hereby certify that Coastal Oil & Gas Corporation is authorized by the proper Lease Interest Owners to conduct lease operations associated with this Application for Permit to Drill the NBU #162, Federal Lease # UTU-4478. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Coastal Oil & Gas Corporation, Nationwide Bond # CO-0018, who will be responsible for compliance with all the terms and conditions of that portion of the lease associated with this Application.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

Charles E. Mowry
Charles E. Mowry
(This space for Federal or State office use)

TITLE

District Drilling Manager

DATE

July 25, 1991

PERMIT NO.

43-047-32066

APPROVAL DATE

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

APPROVED BY

TITLE

CONDITIONS OF APPROVAL, IF ANY:

DATE:

8-16-91


BY:

J. D. [Signature]

WELL SPACING: 615-23

*See Instructions On Reverse Side

T10S, R20E, S.L.B.&M.




▲ = SECTION CORNERS LOCATED. (Brass Caps)

COASTAL OIL & GAS CORP.

Well location, NBU #162, located as shown in the SE 1/4 NW 1/4 of Section 12, T10S, R20E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT A ROAD INTERSECTION IN THE NW 1/4 OF SECTION 11, T10S, R20E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NW QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5055 FEET.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert L. Kay
REGISTERED LAND SURVEYOR
REGISTRATION NO. 5709
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
P. O. BOX 1758 - 85 SOUTH - 200 EAST
VERNAL, UTAH - 84078

SCALE 1" = 1000'	DATE 6-26-91
PARTY G.S. B.R. R.E.H.	REFERENCES G.L.O. PLAT
WEATHER HOT	FILE COASTAL OIL & GAS CORP.

COASTAL OIL & GAS CORPORATION
Lease #UTU-4478, NBU #162
SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 12, T10S, R20E
Uintah County, Utah

Drilling Prognosis

1. Estimated Tops of Important Geologic Markers:

Uinta	Surface	Wasatch	4725'
Green River	1725'	Total Depth	6150'

2. Estimated Depths of Anticipated Water, Oil, Gas or Mineral Formations:

Wasatch	4725'	Gas (Primary Objective)
---------	-------	-------------------------

If any shallow water zones are encountered, they will be adequately protected and reported; none anticipated. All potentially productive hydrocarbon zones will be cemented off.

3. Pressure Control Equipment: (Schematic Attached)

A. Type: 11" Double Gate Hydraulic.

The Blow-Out Preventer will be equipped as follows:

1. One (1) blind ram (above).
2. One (1) pipe ram (below).
3. Kill line (2-inch minimum).
4. One (1) kill line valve (2-inch minimum).
5. One (1) choke line valve.
6. Two (2) adjustable chokes.
7. Upper kelly cock valve with handle available.
8. Safety valve & subs to fit all drill strings in use.
9. 2-inch (minimum) choke line.
10. Pressure gauge on choke manifold.

B. Pressure Rating: 2,000 psi

C. Testing Procedure:

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

3. Pressure Control Equipment:

C. Testing Procedure: Continued

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day.

All BOP drills and tests will be recorded in the IADC driller's log.

D. Choke Manifold Equipment:

All choke lines will be straight lines unless turns use tee blocks or are targeted with running tees, and will be anchored to prevent whip and vibration.

E. Accumulator:

The accumulator will have sufficient capacity to close all BOP's and retain 200 psi above precharge. Nitrogen bottles which meet the manufacturer's specifications will be used as the backup to the required independent power source. The accumulator precharge pressure test will be conducted prior to connecting the closing unit to the BOP stack and at least once every six (6) months thereafter. The accumulator pressure will be corrected if the measured precharge pressure is found to be above or below the maximum or minimum limits specified in Onshore Operating Order #2.

F. Special Drilling Operations:

In addition to the equipment already specified in Items A through E, above, the following equipment will be in place and operational during air/gas drilling:

1. Properly lubricated and maintained rotating head.
2. Spark arresters on engines or water cooled exhaust.
3. Bloop line discharge 100 feet from well bore and securely anchored.

3. Pressure Control Equipment:

F. Special Drilling Operations: Continued

4. Straight run on blooie line.
5. Deduster equipment (not required for aerated water system).
6. All cuttings and circulating medium(s) shall be directed into a reserve or blooie pit.
7. Float valve above bit.
8. Automatic igniter or continuous pilot light on the blooie line (not required for aerated water system).
9. Compressors located in the opposite direction from the blooie line and at a minimum of 100 feet from the well bore.
10. Mud circulating equipment, water, and mud materials (does not have to be pre-mixed) sufficient to maintain the capacity of the hole and circulating tanks or pits.

G. Miscellaneous Information:

The Blow-Out Preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of Onshore Operating Order #2.

The choke manifold and BOP extension rods with hand wheels will be located outside the rig sub-structure. The hydraulic BOP closing unit will be located at least twenty-five (25) feet from the well head but readily accessible to the driller.

Exact locations and configurations of the hydraulic BOP closing unit will depend upon the particular rig contracted to drill this hole.

A flare line will be installed after the choke manifold, extending 100 feet (minimum) from the center of the drill hole to a separate flare pit.

4. The Proposed Casing and Cementing Program: (All New)

A. Casing Program

<u>Hole Size</u>	<u>Casing Size</u>	<u>Wt./Ft.</u>	<u>Grade</u>	<u>Joint</u>	<u>Depth Set</u>
12-1/4"	8-5/8"	24.0#	K-55	ST&C	0- 250'

4. The Proposed Casing and Cementing Program: (All New)

A. Casing Program - Continued

<u>Hole Size</u>	<u>Casing Size</u>	<u>Wt./Ft.</u>	<u>Grade</u>	<u>Joint</u>	<u>Depth Set</u>
7-7/8"	5-1/2"	17.0#	K-55	LT&C	0-6150'

Casing string(s) will be pressure tested to 0.22 psi per foot, or 1500 psi (not to exceed 70% of the internal yield strength of the casing), whichever is greater, after cementing and prior to drilling out from under the casing shoe.

B. Cementing Program

Surface Casing : Cement with approximately 180 sx Class "G" cement + additives, circulated to surface with 100% excess.

Production Casing : Lead with approximately 350 sx Halliburton Silica "Lite" cement with 4% Gel, 4% CaCl₂, 0.3 % Halad-413 and 2.0#/sx Granulite TR; tail with approximately 195 sx Class "G" cement + additives. Cement will be circulated back to surface with 30% excess.

Actual cement volumes to be required will be determined from the caliper log.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

5. Mud Program: (Visual Monitoring)

<u>Interval</u>	<u>Type</u>	<u>Weight</u>	<u>Viscosity</u>	<u>Fluid Loss</u>
0-6150'	Aerated Water	-----	-----	-----

Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control during the course of drilling operations.

6. Evaluation Program:

Logs : DIL-Caliper : 6150' - Surface
FDC-CNL : 6150' - 1500'

DST's : None anticipated.

Cores : None anticipated.

The proposed evaluation program may change at the discretion of the wellsite geologist, with prior approval from the Authorized Officer, Bureau of Land Management.

Stimulation : No stimulation or frac treatment has been formulated for this test at this time. The drill site, as approved, will be of sufficient size to accommodate all completion activities.

Whether the well is completed as a dry hole or as a producer, Well Completion and Recompletion Report and Log (Form 3160-4) will be submitted to the Book Cliffs Resource Area Office not later than thirty (30) days after the completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164.

Two (2) copies of all logs, core descriptions, core analyses, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the Authorized Officer, Book Cliffs Resource Area Office, Bureau of Land Management, 170 South 500 East, Vernal, Utah 84078, Phone: (801) 789-1362.

7. Abnormal Conditions:

No abnormal temperatures or pressures are anticipated. No H₂S has been encountered in or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 2,860 psi (calculated at 0.465 psi/foot) and maximum anticipated surface pressure equals approximately 1,507 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. Anticipated Starting Dates and Notification of Operations:

A. Drilling Activity

Anticipated Commencement Date : September 10, 1991
Drilling Days : Approximately 10 Days
Completion Days : Approximately 7 days

B. Notification of Operations

The Book Cliffs Resource Area Office, Bureau of Land Management will be notified at least twenty-four (24) hours PRIOR to the commencement of the following activities:

1. Spudding of the well. This oral report will be followed up with a Sundry Notice (Form 3160-5);
2. initiating pressure tests of the blow-out preventer and related equipment;
3. running casing and cementing of ALL casing strings.

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in suspended status without prior approval of the Authorized Officer. If operations are to be suspended, prior approval of the Authorized Officer will be obtained and notification given before resumption of operations.

In accordance with Onshore Operating Order #1, this well will be reported on MMS Form 3160-6, "Monthly Report of Operations", starting with the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with the Royalty Management Program, Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217.

Immediate Report: spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the provisions of NTL-3A or its current revision.

8. Anticipated Starting Dates and Notification of Operations:

B. Notification of Operations - Continued

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed for prior approval of the Authorized Officer, and all conditions of this approved plan will be applicable during all operations conducted with the replacement rig.

Should the well be successfully completed for production, the Authorized Officer will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication no later than five (5) business days following the date on which the well is placed on production.

Pursuant to NTL-2B, with the approval of the Authorized Officer, produced water may be temporarily disposed of into the reserve pit for a period of up to ninety (90) days. During this period so authorized, an application for approval of the permanent disposal method, along with the required water analysis and other information, must be submitted to the Authorized Officer.

Pursuant to NTL-4A, lessees and operators are authorized to vent/flare gas during initial well evaluation tests, not exceeding a period of thirty (30) days or the production of fifty (50) MMCF of gas, whichever occurs first. An application must be filed with the Authorized Officer, and approval received, for any venting/flaring of gas beyond the initial thirty (30) day or otherwise authorized test period.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the Vernal District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in 43 CFR 3162.7 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

A first production conference will be scheduled within fifteen (15) days after receipt of the first production notice.

8. Anticipated Starting Dates and Notification of Operations:

B. Notification of Operations - Continued

No well abandonment operations will be commenced without the prior approval of the Authorized Officer. In the case of newly-drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the Authorized Officer.



A "Notice of Intention to Abandon" (Form 3160-5) will be filed with the Authorized Officer within fifteen (15) days following the granting of oral approval to plug and abandon.

Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR 3162.6. The following information will be permanently placed on the marker with a plate, cap, or beaded-on with a welding torch: "Fed" or "Ind", as applicable; Company Name, Well Name and Number, Location by Quarter/Quarter, Section, Township, Range, and Federal or Indian Lease Number.

A "Subsequent Report of Abandonment" (Form 3160-5) will be submitted within thirty (30) days following the actual plugging of the well bore. This report will indicate where plugs were placed and the current status of surface restoration operations. If surface restoration has not been completed at that time, a follow-up report on Form 3160-5 will be filed when all surface restoration work has been completed and the location is considered ready for final inspection. Final abandonment will not be approved until the surface reclamation work required by the approved Application for Permit to Drill has been completed to the satisfaction of the Authorized Officer or his representative, or the appropriate Surface Management Agency.

Pursuant to Onshore Operating Order #1, lessees and operators have the responsibility to see that their exploration, development, production, and construction operations are conducted in such a manner which conforms with applicable Federal laws and regulations and with State and local laws and regulations to the extent that such State and local laws are applicable to operations on Federal and Indian lands.

BOP STACK



COASTAL OIL & GAS CORPORATION
Lease #UTU-4478, NBU #162
SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 12, T10S, R20E
Uintah County, Utah

Multi-Point Surface Use and Operations Plan

1. Existing Roads: Refer to Maps "A" & "B" (shown in ORANGE)
 - A. The proposed well site is staked and four 200-foot reference stakes are present.
 - B. To reach the location from the town of Vernal, Utah; proceed generally southwest approximately 14.0 miles on U.S. Highway 40 (a paved U.S. highway), thence generally south approximately 17.0 miles on Utah Highway 88 (a paved state highway) to the community of Ouray, thence generally south approximately 9.9 miles on the Seep Ridge Road (an existing, upgraded Uintah County road), thence generally northeast approximately 0.8 miles on an existing, upgraded oilfield road (crowned & ditched with a gravel surface), thence generally southeast approximately 0.4 miles to the proposed NBU #162 well location.
 - C. Access roads - refer to Maps "A" and "B".
 - D. Access roads within a one (1) mile radius - refer to Map "B".
 - E. The existing gravel roads will be maintained in the same or better condition as existed prior to the commencement of operations and said maintenance will continue until final abandonment and reclamation of the NBU #162 well location.

2. Planned Access Roads: Refer to Map "B" (Shown in GREEN)

Approximately 0.4 miles of new road construction will be required for access to the proposed NBU #162 well location.

- A. Width - maximum 30-foot overall right-of-way with an 18-foot road running surface, crowned & ditched.
- B. Construction standard - the access road will be constructed in accordance with Bureau of Land Management Roding Guidelines established for oil and gas exploration and development activities as referenced in the BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Third Edition.

The access road will be constructed to meet the standards of the anticipated traffic flow and all-weather requirements. Construction will include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed and safe road.

2. Planned Access Roads:

B. Construction standard - continued

The access road will be constructed to meet the standards of the anticipated traffic flow and all-weather requirements. Construction will include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed and safe road.

Prior to construction/upgrading, the roadway shall be cleared of any snow cover and allowed to dry completely.

Traveling off of the thirty (30) foot right-of-way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or the accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at a frequent intervals by means of cutouts.

Upgrading shall not be allowed during muddy conditions.

Should mud holes develop, they shall be filled in and detours around them avoided.

- C. Maximum grade - 5%.
- D. Turnouts - turnouts will be constructed along the access route as necessary or required to allow for the safe passage of traffic. None anticipated at this time.
- E. Drainage design - the access road will be crowned, ditched, and water turnouts installed as necessary to provide for proper drainage along the access road route.
- F. Culverts, cuts and fills - no culverts will be required. There are no major cuts and/or fills on/along the proposed access road route.
- G. Surface materials - any construction materials which may be required for surfacing of the access road will be purchased from a local contractor having a permitted source of materials in the area, if required by the Authorized Officer, Bureau of Land Management. None anticipated at this time.

2. Planned Access Roads: Continued

- H. Gates, cattleguards or fence cuts - none required.
- I. Road maintenance - during both the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and will be maintained in accordance with the original construction standards. All drainage ditches and culverts will be kept clear and free-flowing, and will also be maintained in accordance with the original construction standards.

The access road right-of-way will be kept free of trash during operations.

- J. The proposed access road has been centerline staked.

3. Location of Existing Wells Within a One-Mile Radius:

Please Refer to Map "C"

- A. Water wells - none known.
- B. Abandoned wells - NW $\frac{1}{4}$ SE $\frac{1}{4}$, Section 12, T10S, R20E.
NW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 13, T10S, R20E.
- C. Temp. abandoned wells - SE $\frac{1}{4}$ SE $\frac{1}{4}$, Section 1, T10S, R20E.
- D. Disposal wells - none known.
- E. Drilling wells - none known.
- F. Producing wells - NE $\frac{1}{4}$ SW $\frac{1}{4}$, Section 1, T10S, R20E.
SW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 11, T10S, R20E.
NE $\frac{1}{4}$ SW $\frac{1}{4}$, Section 11, T10S, R20E.
NW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 12, T10S, R20E.
NW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 12, T10S, R20E.
NE $\frac{1}{4}$ NE $\frac{1}{4}$, Section 13, T10S, R20E.
SW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 13, T10S, R20E.
SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 7, T10S, R21E.
- G. Shut-in wells - none known.
- H. Injection wells - none known.
- I. Monitoring wells - none known.

4. Location of Existing and/or Proposed Facilities Owned by Coastal Oil & Gas Corporation Within a One-Mile Radius:

A. Existing

- 1. Tank batteries - NE $\frac{1}{4}$ SW $\frac{1}{4}$, Section 1, T10S, R20E.
NW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 12, T10S, R20E.
NW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 12, T10S, R20E.
NE $\frac{1}{4}$ NE $\frac{1}{4}$, Section 13, T10S, R20E.

4. Location of Existing and/or Proposed Facilities Owned by Coastal Oil & Gas Corporation Within a One-Mile Radius:

A. Existing - Continued

1. Tank batteries - SW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 13, T10S, R20E.
SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 7, T10S, R21E.
2. Production facilities - same as Item #4A1, above.
3. Oil gathering lines - none.
4. Gas gathering lines - same as Item #4A1, above.

B. New Facilities Contemplated

1. All production facilities will be located on the disturbed portion of the well pad and at a minimum of twenty-five (25) feet from the toe of the back-slope or top of the fill slope.
2. The production facilities (consisting primarily of a christmas tree at the well head, dehydration unit, and emergency pit) will require an area approximately 300' X 135'. A diagram showing the proposed production facility layout will be submitted to the Authorized Officer via "Sundry Notice" (Form 3160-5) for approval of subsequent installation operations.
3. Production facilities will be accommodated on the existing well pad. Construction materials required for installation of the production facilities will be obtained from the site; any additional materials required will be purchased from a local supplier having a permitted (private) source of materials within the area.

A dike will be constructed completely around the production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

4. All permanent (on-site for six months or longer) above-the-ground structures constructed or installed including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Five (5) State Rocky Mountain Interagency Committee. All production facilities will be painted within six (6) months of installation.

4. Location of Existing and/or Proposed Facilities Owned by Coastal Oil & Gas Corporation Within a One-Mile Radius:

B. New Facilities Contemplated - Continued

4. Facilities required to comply with Occupational Health and Safety Act Rules and Regulations will be excluded from this painting requirement.

The required paint color is Carlsbad Canyon, Munsell standard color number 2.5Y 6/2.

5. If at any time the facilities located on public lands and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), the Bureau of Land Management will process a change in authorization to the appropriate statute). The authorization will be subject to the appropriate rental or other financial obligation as determined by the Authorized Officer.

- C. The production (emergency) pit will be fenced with woven wire mesh topped with one (1) strand of barbed wire held in place with metal side posts and wooden corner "H" braces in order to protect livestock and wildlife. Please refer to Item #9E (page #'s 8 & 9) for additional information on the fencing specifications.
- D. During drilling and subsequent operations, all equipment and vehicles will be confined to the access road right-of-way and any additional areas as specified in the approved Application for Permit to Drill.
- E. Reclamation of disturbed areas no longer needed for operations will be accomplished by grading, leveling and seeding as recommended by the Bureau of Land Management.

5. Location and Type of Water Supply:

- A. Fresh water for drilling will be obtained from an existing water well and reservoir: Uintah #1, owned by Target Trucking, Inc. and located in the SE $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$ of Section 16, Township 10 South, Range 21 East, Uintah County, Utah; permit #49-991 (A57530).
- B. Water will be transported over existing roads via tank truck from the point of diversion to the proposed NBU #162 well location.

5. Location and Type of Water Supply: Continued

- B. No new construction will be required on/along the proposed water haul route. No off-lease/unit federal lands will be crossed on/along the proposed water haul route.
- C. No water well will be drilled on this location.

6. Source of Construction Materials:

- A. Construction materials needed for surfacing of the well pad will be obtained from a local contractor having a permitted (private) source of materials in the area. Refer to Item #2G (page #2) regarding any construction materials which may be required on the access road.
- B. No construction materials will be taken from Federal and/or Indian lands without prior approval from the appropriate Surface Management Agency.
- C. If production is established, any additional construction materials needed for surfacing the access road and installation of production facilities will be purchased from a local supplier having a permitted (private) source of materials in the area.
- D. No new access roads for construction materials will be required.

7. Methods of Handling Waste Materials:

- A. Cuttings - the cuttings will be deposited in the reserve/bloolie pit.
- B. Drilling fluids - including salts and chemicals will be contained in the reserve/bloolie pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within ninety (90) days after termination of drilling and completion activities.

In the event adverse weather conditions prevent removal of the fluids from the reserve pit within this time period, an extension may be granted by the Authorized Officer upon receipt of a written request from Coastal Oil & Gas Corporation.

The reserve pit will be constructed so as not to leak, break, or allow discharge.

7. Methods of Handling Waste Materials: Continued

- C. Produced fluids - liquid hydrocarbons produced during completion operations will be placed in test tanks on the location. Produced waste water will be confined to a lined pit (reserve pit) or storage tank for a period not to exceed ninety (90) days after initial production.

During the ninety (90) day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with the required water analysis, shall be submitted for the Authorized Officer's approval. Failure to file an application within the time frame allowed will be considered an incidence of noncompliance.

Any spills of oil, gas, salt water or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

- D. Sewage - self-contained, chemical toilets will be provided by Rocket Sanitation for human waste disposal. Upon completion of operations, or as needed, the toilet holding tanks will be pumped and the contents thereof disposed of in the nearest, approved, sewage disposal facility.
- E. Garbage and other waste material - garbage, trash and other waste materials will be collected in a portable, self-contained and fully-enclosed trash cage during drilling and completion operations. Upon completion of operations (or as needed) the accumulated trash will be disposed of at an authorized sanitary landfill. No trash will be burned on location or placed in the reserve pit.
- F. Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned up and removed from the well location. No adverse materials will be left on the location upon the termination of drilling and completion operations.

Any open pits will be fenced during the drilling operation and the fencing will be maintained until such time as the pits are backfilled.

8. Ancillary Facilities:

None anticipated.

9. Wellsite Layout:

- A. Figure #1 shows the drill site layout as staked. Cross sections have been drafted to visualize the planned cuts and fills across the location. A minimum of six (6) inches of topsoil will be stripped from the location (including areas of cut, fill, and/or subsoil storage) and stockpiled for future reclamation of the well site. Refer to Figure #1 for the location of the topsoil and subsoil stockpiles.
- B. Figure #1 is a diagram showing the rig layout. No permanent living facilities are planned. There will be one (1) trailer on location during drilling operations for the toolpusher.
- C. A diagram showing the proposed production facility layout will be submitted to the Authorized Officer via Sundry Notice (Form 3160-5) for approval of subsequent operations. Please refer to Item #4B2 (page #4) for additional information in this regard.
- D. If porous subsoil materials (gravel, scoria, sand, faulted rock structures, etc.) are encountered during reserve pit construction, an impervious liner will be installed in order to prevent drilling water loss through seepage. We do not anticipate the need for a pit liner at this time.
- E. Prior to the commencement of drilling operations, the reserve pit will be fenced "sheep tight" on three (3) sides according to the following minimum standards:
 - 1. 39-inch net wire shall be used with at least one (1) strand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
 - 2. The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least 42 inches.
 - 3. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
 - 4. Standard steel, wood, or pipe posts shall be used between the corner braces. maximum distance between any two (2) posts shall be no greater than sixteen (16) feet.

9. Wellsite Layout: Continued

E. Prior to the commencement of drilling operations, the reserve pit will be fenced "sheep tight" on three (3) sides according to the following minimum standards:

5. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The fourth side of the reserve pit will be fenced immediately upon removal of the drilling rig and the fencing will be maintained until the pit is backfilled.

F. Any hydrocarbons on the pit will be removed from the pit as soon as possible after drilling operations are completed.

10. Plans for Reclamation of the Surface:

A. Production

1. Immediately upon well completion, the well location and surrounding area(s) will be cleared of all debris, materials, trash and junk not required for production.
2. Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.
3. If a plastic or nylon reinforced pit liner is used, it shall be torn and perforated before backfilling of the reserve pit.
4. Before any dirt work to restore the location takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc. will be removed. Other waste and spoil materials will be disposed of immediately upon completion of drilling and workover activities.
5. The reserve pit and that portion of the location and access road not needed for production facilities/operations will be reclaimed within ninety (90) days from the date of well completion, weather permitting.

10. Plans for Reclamation of the Surface:

A. Production - Continued

6. For production, the fill slopes will be reduced from a 1.5:1 slope to a 4:1 slope and the cut slopes will be reduced from a 1.5:1 slope to a 4:1 slope by pushing the fill material back up into the cut.
7. Upon completion of backfilling, leveling and re-contouring, the stockpiled topsoil will be evenly spread over the reclaimed area(s). Prior to reseeding, all disturbed surfaces (including the access road and location) will be scarified and left with a rough surface. No depressions will be left that would trap water and form ponds. All disturbed surfaces (including the access road and well pad areas) will be reseeded with a seed mixture to be recommended by the Authorized Officer, Bureau of Land Management.

Seed will be drilled on the contour to an approximate depth of one-half (1/2) inch. All seeding will be conducted after September 15 and prior to ground frost.

B. Dry Hole/Abandoned Location

1. At such time as the well is physically plugged and abandoned, Coastal Oil & Gas Corporation will submit a "Subsequent Report of Abandonment" to the Authorized Officer for approval. At that time, the Bureau of Land Management will formulate the appropriate surface rehabilitation requirements and attach them as the conditions of approval for final abandonment.

11. Surface Ownership:

The well site and proposed access road are situated on surface estate which is owned by the United States of America and administered by:

Area Manager
Book Cliffs Resource Area Office
Bureau of Land Management
170 South 500 East
Vernal, Utah 84078
Phone: (801) 789-1362

12. Other Information:

- A. General Description of the Project Area: The proposed drill site is located within the Natural Buttes Unit in an area of northeastern Utah and more specifically in an area of moderately to severely eroded uplands located between the White River to the east (and north), the Green River to the west, both Cottonwood and Sand Washes and Willow Creek to the west.

This area is classified as a "High Plains Steppe" (Cold Desert) and is characterized by gently to moderately undulated uplands dissected by numerous dendritically-patterned, ephemeral drainages of both the Green and White Rivers. Generally, local flora consists of native grasses such as salt grass, galleta grass, needle-and-thread grass, Indian ricegrass; and woody species such as shadscale, horsebrush, black sagebrush, fringe sagebrush, big sagebrush, rabbitbrush, and greasewood along the dry drainages. Local fauna consists of mule deer, antelope, coyotes, rabbits, raptors, and various smaller vertebrate and invertebrate species.

There are no known threatened or endangered species that will be affected by implementation of operations on the proposed NBU #162 well location.

- B. Surface Use Activities: The primary surface use is for grazing.
- C. Proximity of Water, Occupied Dwellings, Archaeological, Historical or Cultural Sites:
1. The closest source of permanent water is the White River, located approximately seven (7) miles to the north.
 2. The closest occupied dwellings are located in the community of Ouray, approximately eight (8) miles to south/southeast.
 3. Coastal Oil & Gas Corporation will be responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites or for collecting artifacts.

12. Other Information:

C. Proximity of Water, Occupied Dwellings, Archaeological, Historical or Cultural Sites: Continued

3. If historic or archaeological materials are uncovered, Coastal Oil & Gas Corporation will suspend all operations that might further disturb such materials and immediately contact the Authorized Officer.

Within five (5) working days the Authorized Officer will inform Coastal Oil & Gas Corporation as to:

- whether the materials appear eligible for the National Register of Historic Places;
- the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and
- a time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If Coastal Oil & Gas Corporation wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, Coastal Oil & Gas Corporation will be responsible for mitigation costs.

The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that the required mitigation has been completed, Coastal Oil & Gas Corporation will then be allowed to resume construction.

12. Other Information: Continued

D. Additional Stipulations for Operations on Lands
Administered by the Bureau of Land Management:

1. Coastal Oil & Gas Corporation will control noxious weeds along rights-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the Bureau of Land Management, or the Uintah County Extension Office. On lands administered by the Bureau of Land Management, it is required that a "Pesticide Use Proposal" shall be submitted, and approval obtained, prior to the application of herbicides or other pesticides or possible hazardous chemicals for the control of noxious weeds.
2. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on federal lands after conclusion of drilling operations or at any other time without the proper authorization from the Bureau of Land Management. However, if BLM authorization is obtained, it is only a temporary measure to allow Coastal Oil & Gas Corporation the time to make arrangements for permanent storage at a commercial facility.
3. No construction or drilling activities shall be conducted between May 15 and June 20 in order to protect crucial Antelope kidding areas.
4. This area as been identified as having critical to severe soil erosion conditions. In order to minimize watershed damage, construction and drilling activities will not be allowed when soils are wet and/or muddy.
5. Coastal Oil & Gas Corporation shall contact the Bureau of Land Management between 24 and 48 hours prior to commencement of construction activities on the access road and/or well location: (801) 789-1362.
6. The Bureau of Land Management shall be notified upon site completion and prior to moving drilling tools onto the location.

12. Other Information:

D. Additional Stipulations for Operations on Lands
Administered by the Bureau of Land Management: Cont.

7. One (1), or possibly two (2), erosion control structure(s) will be constructed in minor drainages along the proposed access road route. The actual location of these erosion control structures will be determined by the Bureau of Land Management at the time of access road and well pad construction.

13. Lessee's or Operator's Representative and Certification:

Representative

Coastal Oil & Gas Corporation
Randy L. Bartley, Operations Manager
P.O. Box 749
Denver, Colorado 80201-0749
Phone: (303) 572-1121

Heitzman Drill-Site Services*
Dale Heitzman and/or Robert M. Anderson
P.O. Drawer 3579
Casper, Wyoming 82602
Phone: (307) 266-4840

- * Contact for any additional information which may be required for approval of this Application for Permit to Drill.

Certification:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil & Gas Orders, the approved plan of operations, and any applicable Notice to Lessees.

Coastal Oil & Gas Corporation will be fully responsible for the actions of their subcontractors.

A complete copy of the approved Application for Permit to Drill will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.


13. Lessee's or Operator's Representative and Certification:

Certification: Continued

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Coastal Oil & Gas Corporation, its' contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

August 1, 1991
Date


Robert M. Anderson/Authorized Agent




TOPOGRAPHIC
MAP "A"


DATE 6-26-91 R.E.H.



COASTAL OIL & GAS CORP.

NBU #162
SECTION 12, T10S, R20E, S.L.B.&M.
REVISED 7-15-91 R.E.H.





LEGEND:

- ◊ = Water Wells
- ◆ = Abandoned Wells
- ◐ = Temporarily Abandoned Wells
- ◑ = Disposal Wells
- = Drilling Wells
- = Producing Wells
- ◑ = Shut-in Wells

COASTAL OIL & GAS CORP.


NBU #162

SECTION 12, T10S, R20E, S.L.B.&M.

T O P O M A P " C "

DATE: 6-26-91 R.E.H.

Proposed Access Road



APPROXIMATE YARDAGES

CUT		
(6") Topsoil Stripping	=	1,070 Cu. Yds.
Remaining Location	=	5,590 Cu. Yds.
TOTAL CUT	=	6,660 CU.YDS.
FILL	=	1,350 CU.YDS.


EXCESS MATERIAL AFTER		
5% COMPACTION	=	5,240 Cu. Yds.
Topsoil & Pit Backfill	=	2,190 Cu. Yds.
(1/2 Pit Vol.)		
EXCESS UNBALANCE	=	3,050 Cu. Yds.
(After Rehabilitation)		

COASTAL OIL & GAS CORP.





LOCATION LAYOUT FOR

NBU #162

SECTION 12, T10S, R20E, S.L.B.&M.



SCALE: 1" = 50'
DATE: 6-27-91
Drawn By: R.E.H.



TYP. LOCATION LAYOUT
TYP. CROSS SECTIONS

FIGURE #1

NOTES:

Elev. Ungraded Ground At Loc. Stake = 5053.3'

FINISHED GRADE ELEV. AT LOC. STAKE = 5052.8'

UINTAH ENGINEERING & LAND SURVEYING
85 South 200 East Vernal, Utah

OPERATOR Coastal Oil Gas Corp 10230 DATE 8-12-91


WELL NAME NB 1162

SEC SE 1/4 T 10S R 10E COUNTY Montah


43-047-30066
API NUMBER

Natural (1)
TYPE OF LEASE

CHECK OFF:



PLAT.



BOND



NEAREST
WELL



LEASE



FIELD
SLBM




POTASH OR
OIL SHALE

PROCESSING COMMENTS:

Included in 91 supplement P.O.D. approved 7-31-91
water permit 44-991 (R57530) target ducking
Oil shale area

APPROVAL LETTER:

SPACING:




R615-2-3

Natural Buttes
UNIT



R615-3-2



N/A
CAUSE NO. & DATE



R615-3-3

STIPULATIONS:

1- Oil shale



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Norman H. Bangerter
Governor

Dee C. Hansen
Executive Director

Dianne R. Nielson, Ph.D.
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

August 16, 1991

Coastal Oil & Gas Corporation
P. O. Box 749
Denver, Colorado 80201-0749

Gentlemen:

Re: NBU #162 Well, 1980 feet from the North line, 1800 feet from the West line, SE NW, Section 12, Township 10 South, Range 20 East, Uintah County, Utah

Approval to drill the referenced well is hereby granted in accordance with Utah Code Ann. Section 40-6-18, et seq. (1953, as amended), and Utah Admin. R.615-2-3, subject to the following stipulation:

1. Special attention is directed to compliance with Utah Admin. R.615-3-34, which prescribes drilling procedures for designated oil shale areas.

In addition, the following actions are necessary to fully comply with this approval:


1. Spudding notification within 24 hours after drilling operations commence.
2. Submittal of Entity Action Form 6, within five working days following spudding and whenever a change in operations or interests necessitates an entity status change.
3. Submittal of the Report of Water Encountered During Drilling, Form 7.
4. Prompt notification in the event it is necessary to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801) 538-5340, (Home) (801) 476-8613, or R. J. Firth, Associate Director, (Home) (801) 571-6068.
5. Compliance with the requirements of Utah Admin. R.615-3-20, Gas Flaring or Venting.

Page 2
Coastal Oil & Gas Corporation
NBU #162
August 16, 1991

6. Prior to commencement of the proposed drilling operations, plans for facilities for disposal of sanitary wastes at the drill site shall be submitted to the local health department. These drilling operations and any subsequent well operations must be conducted in accordance with applicable state and local health department regulations. A list of local health departments and copies of applicable regulations are available from the Department of Environmental Quality, Division of Drinking Water/Sanitation, telephone (801) 538-6159.
7. This approval shall expire one (1) year after date of issuance unless substantial and continuous operation is underway or an application for an extension is made prior to the approval expiration date.

The API number assigned to this well is 43-047-32066.

Sincerely,



R. J. Firth
Associate Director, Oil & Gas

tas
Enclosures
cc: Bureau of Land Management
J. L. Thompson
we14/1-7

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1A. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

B. TYPE OF WELL

OIL
WELL ☐

GAS
WELL ☒

OTHER

SINGLE
ZONE ☒

MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR

P. O. Box 749, Denver, Colorado 80201-0749

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

1980' FNL, 1800' FWL (SE $\frac{1}{4}$ NW $\frac{1}{4}$) Section 12, T10S, R20E

At proposed prod. zone

Same As Above

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately Eight (8) Miles South/Southeast of Ouray, Utah

10. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST

PROPERTY OR LEASE LINE, FT.

(Also to nearest drig. unit line, if any)

1800'

16. NO. OF ACRES IN LEASE

320

17. NO. OF ACRES ASSIGNED

TO THIS WELL
80

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

2100'±

19. PROPOSED DEPTH

6150'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5053' GR

22. APPROX. DATE WORK WILL START*

September 10, 1991

23.

(ALL NEW)

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" K-55	24.0#	0- 250'	180 sx Circ. to Surface *
7-7/8"	5-1/2" K-55	17.0#	0- 6150'	545 sx Circ. to Surface *

* Cement volumes may change due to hole size.
Calculate from Caliper log.

EIGHT-POINT RESOURCE PROTECTION PLAN ATTACHED.

I hereby certify that Coastal Oil & Gas Corporation is authorized by the proper Lease Interest Owners to conduct lease operations associated with this Application for Permit to Drill the NBU #162, Federal Lease # UTU-4478. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Coastal Oil & Gas Corporation, Nationwide Bond # CO-0018, who will be responsible for compliance with all the terms and conditions of that portion of the lease associated with this Application.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

Charles E. Mowrey
Charles E. Mowrey

TITLE

District Drilling Manager

DATE

July 25, 1991

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

Ronald D. Chavez

TITLE

ASSISTANT DISTRICT
MANAGER MINERALS

DATE

AUG 15 1991

CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF APPROVAL

*See Instructions On Reverse Side

CONDITIONS OF APPROVAL ATTACHED
TO OPERATOR'S COPY

CONDITIONS OF APPROVAL
FOR APPLICATION FOR PERMIT TO DRILL

Company/Operator: Coastal Oil & Gas

Well Name & Number: NBU-162

Lease Number: U-4478

Location: SENW, Sec. 12, T10S, R20E

Surface Ownership: BLM

NOTIFICATION REQUIREMENTS

- | | | |
|---------------------------------|---|--|
| Location Construction | - | at least forty-eight (48) hours prior to construction of location and access roads. |
| Location Completion | - | prior to moving on the drilling rig. |
| Spud Notice | - | at least twenty-four (24) hours prior to spudding the well |
| Casing String and Cementing | - | at least twenty-four (24) hours prior to running casing and cementing all casing strings. |
| BOP and Related Equipment Tests | - | at least twenty-four (24) hours prior to initiating pressure tests. |
| First Production Notice | - | within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days. |

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 feet above the top of the Mahogany oil shale, identified at + 2190 feet.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the Authorized Officer. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the Authorized Officer (AO).

A cement bond log (CBL) shall be utilized to determine the top of cement (TOC) and bond quality for the production casing.

6. Notifications of Operations

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells, as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated, or the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of thirty (30) days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the AO. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

All site security regulations, as specified in Onshore Oil and Gas Order No. 3, shall be adhered to.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the A0.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The A0 will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the A0. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka Petroleum Engineer	(801) 781-1190
---	----------------

Ed Forsman Petroleum Engineer	(801) 789-7077
----------------------------------	----------------

BLM FAX Machine	(801) 789-3634
-----------------	----------------

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous:

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids.

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt wastes.

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation, and miscellaneous solids

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone No.

P. O. Box 749, Denver, CO 80201-0749 (303) 573-4478

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1980' FNL 1800' FWL Sec. 12, T10S R20E

FORM APPROVED

Budget Bureau No. 1004-0135

Expires: September 30, 1990

5. Lease Designation and Serial No.

UTU-4478

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

Natural Buttes

8. Well Name and No.

NBU #162

9. API Well No.

13-047-32066

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection

Change drilling prognosis

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Coastal requests a variance to the existing rules and regulations requiring the blooie line to be not less than 100' from the borehole.

This well is being drilled with air mist injecting water at the rate of 15-20 gpm until they reach the lost circulation zone. Then the rig pumps are utilized using aerated water at the rate of 190 gpm to total depth.

RECEIVED

OCT 03 1991

COPY

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed

Steve Hertzman

Title

Authorized Agent

Date August 23, 1991

(This space for Federal or State office use)

Approved by

Tim Chugwell

Title

acting

ASSISTANT DISTRICT
MANAGER MINING

Date OCT 02 1991

Conditions of approval, if any:

CONDITIONS OF APPROVAL ATTACHED
TO OPERATOR'S COPY

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side

Coastal Oil & Gas Corp.
Well No. NBU 162
Lease U-4478

CONDITIONS OF APPROVAL

We have reviewed your proposal for technical adequacy and concur with the request providing the following stipulations are included as a part of the approval.

1. Your request is approved to a depth of 1500 ft.
2. Air mist drilling will not be allowed below a depth of 1500 ft. unless the blooie line is extended out at least 100 ft. from the well bore as per the requirements of Onshore Oil and Gas Order No. 2.

RECEIVED

OCT 03 1991

DIVISION OF
OIL GAS & MINING

WATER PERMIT OK

DIVISION OF OIL, GAS AND MINING

API NO. 43-047-32066

SPODDING INFORMATION

NAME OF COMPANY: COASTAL OIL & GAS CORPORATION

WELL NAME: NBU 162

SECTION SENE 12 TOWNSHIP 10S RANGE 20E COUNTY UINTAH

DRILLING CONTRACTOR COASTAL

RIG # 1

SPODDED: DATE 10-16-91

TIME 4:00 p.m.

HOW DRY HOLE

DRILLING WILL COMMENCE 10-24-91

REPORTED BY STEVE/LEON ROSS

TELEPHONE # 722-4469

DATE 10-17-91 SIGNED TAS/SBH

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone No.

P. O. Box 749 Denver, CO 80201-0749 (303) 573-4476

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1930' FNL & 1800' FWL (SE/NW)
Section 12, T10S-R20E

5. Lease Designation and Serial No.

UTU-4478

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

Natural Buttes Unit

8. Well Name and No.

NBU #162

9. API Well No.

43-047-32066

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah County, Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other Report of Spud

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

HIRU Leon Ross Drilling. Drilled 12-1/4" surface hole to 263' KB. Ran 6 jts 8-5/8" 24 1/2 K-55 ST&C casing and set @ 263'. Cemented w/150 sx Type V cement + additives.

RECEIVED

NOV 07 1991

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed

Title

Regulatory Analyst

Date

11/5/91

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR Coastal Oil & Gas Corporation
ADDRESS P. O. Box 749
Denver, CO 80201-0749

OPERATOR ACCT. NO. N0230

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	2900	→	43-047-32066	NBU #162	SE/NW	12	10S	20E	Uintah	10/17/91	10/17/91
WELL 1 COMMENTS: <i>Federal-Lease Prop. Zone-WSTC</i> <i>Field-Natural Buttes (Entity 2900 added 11-12-91) Jc</i> <i>Unit-Natural Buttes</i>											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

RECEIVED

NOV 07 1991

DIVISION OF
OIL GAS & MINING

Eileen Danni Dey
Signature Eileen Danni Dey

Regulatory Analyst 11/5/91
Title Date

Phone No. (303) 573-4476

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.

UTU-4478

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

Natural Buttes Unit

8. Well Name and No.

NBU #162

9. API Well No.

43-047-32066

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah County, Utah

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone No.

P. O. Box 749 Denver, CO 80201-0749 (303) 573-4476

4. Location of Well (Foxage, Sec., T., R., M., or Survey Description)

1980' FNL & 1800' FWL (SE/NW)
Section 12, T10S-R20E

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other Report of Operations
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please see the attached chronological report for the drilling operations performed on the above referenced well.

RECEIVED

NOV 25 1991

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed

William K. Kautsky Title Regulatory Analyst

Date 11/20/91

(This space for Federal or State Office use)

Approved by

Conditions of approval, if any:

Title

Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side

COASTAL OIL & GAS CORPORATION
CHRONOLOGICAL HISTORY

NBU #162
NATURAL BUTTES UNIT
UINTAH COUNTY, UTAH
COASTALDRIL #1
WI: 60% COGC AFE: 13174
ATD: 6200' (WASATCH) SD: 11/3/91
CSG: 8-5/8" @ 244'
DHC(M\$): 158.9

- 11/3/91 Drlg cmt. Move and RURT's. Test BOPE to 2000# - OK. No BLM witness. PU BHA. Drlg cmt @ 247'. Air compressor will not start. Drlg w/wtr. CC: \$30,502.
- 11/4/91 1550' Drlg 1282'/21 hrs. Drill cmt & FS @ 268'. Drlg, wtr only. Svys: 1/4 deg @ 489'; 2 deg @ 1110'; 2-3/4 deg @ 1455'. Chg propane line. Drlg w/air mist. Spud @ 7:00 a.m., 11/3/91. 1200 CFM. CC: \$38,431.
(NOTE: Verbal report given this date to CEM that surface was spudded w/Leon Ross @ 10:30 a.m. on 10/17/91.)
- 11/5/91 2830' Drlg 1280'/20.5 hrs. Drlg, svys: 2-1/4 deg @ 1552'; 2-3/4 deg @ 2057'; 2-3/4 deg @ 2595'. Water @ 2607'. Svy, pull string float. Thaw propane lines. Drlg w/aerated wtr. 1200 CFM. CC: \$44,809.
- 11/6/91 3720' Drlg 890'/23 hrs. Drlg, svy: 1-1/2 deg @ 3070'. RS, check BOP, drlg. MW 8.4, VIS 27, WL N/C, PH 11. CC: \$52,125.
- 11/7/91 4460' Drilling 740'/22.5 hrs. Drlg, svys: 1-1/2 deg @ 3698'; 2 deg @ 4230'. RS, check BOP. Drlg. MW 8.4, VIS 27, WL N/C, PH 11.0. CC: \$62,432.
- 11/8/91 5045' Drlg 585'/23 hrs. Drlg, RS & check BOP's. Drlg, svy: 1-1/2 deg @ 4833'. Drlg w/wtr. PH 11.0. CC: \$67,472.
- 11/9/91 5540' Drlg 495'/18 hrs. Drlg, TFNB. LD SS & 1 DC. PU DC and check BOP's. RS, drlg, svys: misrun @ 5390'; 1-1/2 deg @ 5486'. Drlg w/wtr, pH 11.0. CC: \$82,122.
- 11/10/91 6185' Drlg 645'/23.5 hrs. Drlg, RS. Drlg brks from 5659'-5670' & 5902'-5924'. Drlg w/wtr, pH 11. CC: \$89,076.
- 11/11/91 6200' LD DC's. 15'/1 hr. Drlg, circ. Short trip 15 stds. Bridge @ 6155'. Circ & displ hole w/10# brine. Drop svy & SLM out. No correction. RU Atlas and log. Logger's TD 6120'. Ran DLL/GR/Cal from 6120' to surface; CDL/CNL from 6100'-2600'. TIH w/DP & DC. RU LD machine and LD DP & DC's. Brine, MW 10. Svy: 3/4 deg @ 6170'. CC: \$106,502.
- 11/12/91 6200' RD MORT. LD DC's. RIH w/150 jts (6209.23') 5-1/2" 17# J-55 LT&C csg. Circ & cond 6094'-6200'. Cmt w/Howco: 540 sx HyFill std w/1#/sk Capseal, 0.3% HR-7; 600 sx Type H, 50-50 Poz, 2% gel, 10% salt, 0.6% Halad 24, 1#/sk Capseal, 1/4#/sk Floseal; 143 bbls wtr displacement. 70 bbls (100 sx) cmt to surface. Bump plug to 2300#, 500# over @ 1:10 p.m., 11/11/91. Floats held. FS set @ 6198'; FC @ 6155', 10 centralizers. ND BOP, set slips w/100M#. RR 3:00 p.m., 11/11/91. CC: \$179,330. FINAL DRILLING REPORT.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE*

(See other instructions on reverse side)

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐
2. TYPE OF COMPLETION: NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. CENVR. ☐

RECEIVED

JAN 10 1992

2. NAME OF OPERATOR
Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR
P. O. Box 749 Denver, CO 80201-0749

4. LOCATION OF WELL (Report location clearly and in accordance with any State or Federal regulations)
At surface 1980' FNL & 1800' FWL (SE/NW)

At top prod. interval reported below Same as above.

At total depth Same as above.

14. PERMIT NO. 43-047-32066 DATE ISSUED 8/16/91

15. DATE SPUDDED 10/17/91 16. DATE T.D. REACHED 11/10/91 17. DATE COMPL. (Ready to prod.) 11/21/91

18. ELEVATIONS (DF, RND, RT, GR, ETC.)* 5053' GR, 5065' KB

20. TOTAL DEPTH, MD & TVD 6200' 21. PLUG BACK T.D., MD & TVD 6071'

22. IF MULTIPLE COMPL., HOW MANY* 23. INTERVALS DRILLED BY SFC-TD

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 5113'-5925' (Wasatch)

25. TYPE ELECTRIC AND OTHER LOGS RUN FDC-CNL, CBL-CCL-GR, DLL-GR-CAL 11-20-91

26. CASING RECORD (Report all strings set in well)

27. WAS DISSECTIONAL SURVEY MADE No

28. WAS WELL CORED No

29. LINER RECORD

30. TUBING RECORD

31. PERFORATION RECORD (Interval, size and number)

Perf'd w/4" csg gun, 1 JSPF @ following depths

5113' 5641' 5908'

5120' 5666' 5914'

5126' 5672' 5925'

5136' 5706'

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

33. PRODUCTION

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) SI, WOPLC.

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED Eileen Danni Day

TITLE Regulatory Analyst

DATE 1/7/92

*(See Instructions and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):					38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.		NAME	MEAS. DEPTH	TRUE VERT. DEPTH
					Wasatch	4722'	4722'

COASTAL OIL & GAS CORPORATION
CHRONOLOGICAL HISTORY

NBU #162
NATURAL BUTTES UNIT
UINTAH COUNTY, UTAH
COASTALDRIL #1
WI: 60% COGC AFE: 13174
ATD: 6200' (WASATCH) SD: 11/3/91
CSG: 8-5/8" @ 244'
DHC(MS): 158.9

- 11/3/91 Drlg cmt. Move and RURT's. Test BOPE to 2000# - OK. No BLM witness. PU BHA. Drlg cmt @ 247'. Air compressor will not start. Drlg w/wtr. CC: \$30,502.
- 11/4/91 1550' Drlg 1282'/21 hrs. Drill cmt & FS @ 268'. Drlg, wtr only. Svys: 1/4 deg @ 489'; 2 deg @ 1110'; 2-3/4 deg @ 1455'. Chg propane line. Drlg w/air mist. Spud @ 7:00 a.m., 11/3/91. 1200 CFM. CC: \$38,431.
- (NOTE: Verbal report given this date to CEM that surface was spudded w/Leon Ross @ 10:30 a.m. on 10/17/91.)
- 11/5/91 2830' Drlg 1280'/20.5 hrs. Drlg, svys: 2-1/4 deg @ 1552'; 2-3/4 deg @ 2057'; 2-3/4 deg @ 2595'. Water @ 2607'. Svy, pull string float. Thaw propane lines. Drlg w/aerated wtr. 1200 CFM. CC: \$44,809.
- 11/6/91 3720' Drlg 890'/23 hrs. Drlg, svy: 1-1/2 deg @ 3070'. RS, check BOP, drlg. MW 8.4, VIS 27, WL N/C, PH 11. CC: \$52,125.
- 11/7/91 4460' Drilling 740'/22.5 hrs. Drlg, svys: 1-1/2 deg @ 3698'; 2 deg @ 4230'. RS, check BOP. Drlg. MW 8.4, VIS 27, WL N/C, PH 11.0. CC: \$62,432.
- 11/8/91 5045' Drlg 585'/23 hrs. Drlg, RS & check BOP's. Drlg, svy: 1-1/2 deg @ 4833'. Drlg w/wtr. PH 11.0. CC: \$67,472.
- 11/9/91 5540' Drlg 495'/18 hrs. Drlg, TFNB. LD SS & 1 DC. PU DC and check BOP's. RS, drlg, svys: misrun @ 5390'; 1-1/2 deg @ 5486'. Drlg w/wtr, pH 11.0. CC: \$82,122.
- 11/10/91 6185' Drlg 645'/23.5 hrs. Drlg, RS. Drlg brks from 5659'-5670' & 5902'-5924'. Drlg w/wtr, pH 11. CC: \$89,076.
- 11/11/91 6200' LD DC's. 15'/1 hr. Drlg, circ. Short trip 15 stds. Bridge @ 6155'. Circ & displ hole w/10# brine. Drop svy & SLM out. No correction. RU Atlas and log. Logger's TD 6120'. Ran DLL/GR/Cal from 6120' to surface; CDL/CNL from 6100'-2600'. TIH w/DP & DC. RU LD machine and LD DP & DC's. Brine, MW 10. Svy: 3/4 deg @ 6170'. CC: \$106,502.
- 11/12/91 6200' RD MORT. LD DC's. RIH w/150 jts (6209.23') 5-1/2" 17# J-55 LT&C csg. Circ & cond 6094'-6200'. Cmt w/Howco: 540 sx HyFill std w/1#/sk Capseal, 0.3% HR-7; 600 sx Type H, 50-50 Poz, 2% gel, 10% salt, 0.6% Halad 24, 1#/sk Capseal, 1/4#/sk Floseal; 143 bbls wtr displacement. 70 bbls (100 sx) cmt to surface. Bump plug to 2300#, 500# over @ 1:10 p.m., 11/11/91. Floats held. FS set @ 6198'; FC @ 6155', 10 centralizers. ND BOP, set slips w/100M#. RR 3:00 p.m., 11/11/91. CC: \$179,330. FINAL DRILLING REPORT.

THE COASTAL CORPORATION
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

PAGE 2

NBU #162
SE/NW SECTION 12, T10S, R20E
NATURAL BUTTES UNIT
UINTAH COUNTY, UTAH
WI: 60.000% COGC AFE: 13174
TD: 6200' SD: 11/3/91
CSG: 5-1/2" @ 6198'
PERFS: 5113'-5925' (WASATCH)
CWC(M\$): \$358.8

11/16/91 MIRU Welltech #247.
DC: \$21,220 TC: \$200,550

11/17/91 Prep to run CBL. Finish MIRU CU. TIH w/4-3/4" mill & 195 jts 2-3/8" tbg. Tag PBD @ 6071'. Circ hole w/150 bbis 3% KCl wtr. POOH w/tbg.
DC: \$2,560 TC: \$203,110

11/18/91 Prep to swab. MIRU wireline company. Ran CBL-GR from PBD to surface. TOC @ 150'. PT csg to 5000 psi. Perf Wasatch w/11 holes from 5113' to 5925'. RIH w/2-3/8" tbg. Landed @ 5071'. NO BOP, NU WH. RU Smith Energy. Breakdown perfs w/4000 gals 3% KCl wtr w/22 ball sealers. AIR 6.3 BPM @ 4700 psi. Balled off perfs. Surged off balls and finish job. ISIP 1210 psi, 15 min 780 psi. RD Smith. Flow back well.
DC: \$9,780 TC: \$212,890

11/19/91 Prep to swab. SICP 200 psi, SITP 200 psi. Blew down in one minute. Made 21 swab runs, rec 122 BLW. IFL @ sfc, FFL @ 4500'. Well did not kick off.
DC: \$1,920 TC: \$214,810

11/20/91 Flow tstg well. SICP 1500 psi, SITP 1500 psi. Well kicked off. Unloaded 20 BW in 1 hr. Start flow tstg on 20/64" chk at 2:00 p.m. flwg 200 MCFD, FTP 100 psi, SICP 450 psi, 20/64" chk, 1-1/2 BWPH.
DC: \$870 TC: \$215,680

11/21/91 Flwg 300 MCFD, FTP 100 psi, CP 400 psi, 20/64" chk, dry gas.

11/22/91 SI, waiting on frac. Flwg 300 MCFD, FTP 100 psi, CP 400 psi, 20/64" chk. Killed well. TOH w/tbg. LD tbg. NO BOP, NU WH. RDMO CU. Drop from report until further activity.
DC: \$1,390 TC: \$217,070

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone No.

P. O. Box 749 Denver, CO 80201-0749 (303) 573-4476

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1980' FNL & 1800' FWL (SE/NW)
Section 12, T10S-R20E

5. Lease Designation and Serial No.

UTU-4478

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

Natural Buttes Unit

8. Well Name and No.

NBU #162

9. API Well No.

43-047-32066

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah County, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other Pipeline Right-of-Way
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Coastal Oil & Gas Corporation requests a right-of-way to install a 4" gas pipeline from the NBU #162 gas well and tie into the existing gas pipeline. This right-of-way will be located in Section 12, T10S-R20E within lease UTU-4478 and within the Natural Buttes Unit boundaries. Coastal requests a 30' width easement with a total slope distance of $\pm 41'$. There will be minimum surface disturbance as the pipeline will be laid on the surface. Please see the attached topographic map which illustrates this proposed right-of-way.

RECEIVED

DATE: 1-23-92
BY: J. Matthews

JAN 21 1992


DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed [Signature] Title Regulatory Analyst Date 1/17/92

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:



TOTAL PIPELINE SLOPE DISTANCE = 41'

**TOPOGRAPHIC
MAP "D"**

LEGEND

- EXISTING PIPELINE
- Proposed Pipeline



COASTAL OIL & GAS CORP.

PROPOSED PIPELINE RIGHT-OF-WAY FOR
NBU #162
SECTION 12, T10S, R20E, S.L.B.&M.

DATE: 1-14-92

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

APR 17 1992

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS OIL GAS & MINING

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone No.

P. O. Box 749 Denver, CO 80201-0749 (303) 573-4476

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

See Attached List

5. Lease Designation and Serial No.

See Attached List

6. If Indian, Aillonee or Tribe Name

See Attached List

7. If Unit or CA, Agreement Designation

Natural Buttes Unit

8. Well Name and No.

See Attached List

9. API Well No.

See Attached List

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah County, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment

☐ Recompletion

☐ Plugging Back

☐ Casing Repair

☐ Altering Casing

☒ Other NTL 2B; IV

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut-Off

☐ Conversion to Injection

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Coastal Oil & Gas Corporation hereby requests permission to dispose of produced water in unlined pits per NTL-2B, IV, for the subject wells.

- 1) These wells are completed in the Wasatch formation and produce less than 5 barrels of water per day on a monthly basis.
- 2) Two unlined pits per location will be used due to the size and layout of the locations: 40' x 40' x 8' and 6' x 6' x 6' deep with berms surrounding them. Each pit will be fenced and will have cement corner posts per BLM specifications. (See the attached typical facilities diagram.)
- 3) The average evaporation rate for the area compensated for annual rainfall is 70" per year.
- 4) The estimated percolation rate based on the soil characteristics under and adjacent to the pits is 2-6" per hour.
- 5) The depth of usable water aquifers in this area is approximately 1500'.

14. I hereby certify that the foregoing is true and correct.

Signed

Eileen Danni Rey
Eileen Danni Rey

Approved by

Conditions of approval, if any:

Title

Regulatory Analyst

4/14/92


Accepted by the State
of Utah Division of
Oil, Gas and Mining

Date: 4-29-92

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side

COASTAL OIL & GAS CORP.
NATURAL BUTTES UNIT
TYPICAL FACILITIES LAYOUT
NTL-2B; IV



13-Apr-92

NATURAL BUTTES

JINTAH COUNTY, UTAH

WELL #	LOCATION	QUAD	SEC	TWP	RGE	STATE OR BLM LEASE #	SURFACE	API NUMBER
NBU #103	SENW	10	9	21		U-0141315	UTE	43-047-31956
NBU #104	SENE	16	9	21		ST ML-3282	UTE	43-047-31957
NBU #105	SWSW	17	9	21		U-0575	UTE	43-047-31955
NBU #106	NESW	21	9	21		U-0576	UTE	43-047-31946
NBU #107	SENW	26	9	21		ST ML-01194	STATE	43-047-31916
NBU #108	SESE	19	9	22		U-0284	UTE	43-047-31958
NBU #109	SENE	27	9	21		ST U-01194-A	STATE	43-047-31917
NBU #110	NENE	28	9	21		U-0576	FED.	43-047-31924
NBU #111	SWNW	25	9	21		ST U-01194	STATE	43-047-31920
NBU #112	SESE	33	9	22		U-01191	FED.	43-047-31930
NBU #113	SESE	34	9	22		U-0149077	FED.	43-047-31931
NBU #114	SWSW	5	10	21		U-01393-D	FED.	43-047-31923
NBU #115	NENW	10	10	21		U-0149079	FED.	43-047-31929
NBU #116	NWNW	6	10	22		U-464	FED.	43-047-31925
NBU #117	NENE	10	10	22		ST UT-01197-A	STATE	43-047-31914
NBU #118	SENE	22	9	20		U-0577-B	UTE	43-047-31969
NBU #119	SENW	22	9	20		U-0577-B	UTE	43-047-31973
NBU #120	NWNW	10	9	21		U-0141315	UTE	43-047-31972
NBU #121	NWNE	13	9	21		U-01193	UTE	43-047-
NBU #122	SWSE	13	9	21		U-01193	UTE	43-047-32085
NBU #123	NWNW	15	9	21		U-01188	UTE	43-047-31974
NBU #124	NWNE	16	9	21		ST ML-3282	UTE	43-047-31971
NBU #125	NESE	17	9	21		U-0575	UTE	43-047-32090
NBU #126	NENW	21	9	21		U-0576	UTE	43-047-31962
NBU #127	SWNW	21	9	21		U-0576	UTE	43-047-31963
NBU #128	SWSW	21	9	21		U-0576	UTE	43-047-31964
NBU #129	SENE	22	9	21		U-010950-A	UTE	43-047-31965
NBU #130	SWNW	22	9	21		U-0147566	UTE	43-047-31967
NBU #131	NWSW	23	9	21		U-0149075	UTE	43-047-31966
NBU #132	NWNW	26	9	21		ST U-01194	STATE	43-047-31938
NBU #133	SWNE	28	9	21		U-0576	FED.	43-047-31950
NBU #134	SWSW	28	9	21		U-0576	FED.	43-047-32011
NBU #135	NESE	18	9	22		U-461	UTE	43-047-32089
NBU #136	SWSE	19	9	22		U-0284	UTE	43-047-31968
NBU #137	SESE	30	9	22		ST ML-22935	STATE	43-047-31939
NBU #138A	SENE	33	9	22		U-01191-A	FED.	43-047-32151
NBU #139	SWNE	14	10	21		U-465	FED.	43-047-31948
NBU #140	NWNE	5	10	22		U-01191A	FED.	43-047-31947
NBU #141	SENW	6	10	22		U-464	FED.	43-047-32017
NBU #142	NESE	10	10	22		U-025187	FED.	43-047-32013
NBU #143	NWNE	10	9	21		U-0141315	UTE	43-047-32088
NBU #144	NWNW	23	9	21		U-0149075	UTE	43-047-32044
NBU #145	NWNE	27	9	21		ST U-01194-A	STATE	43-047-31976
NBU #146	SWNW	14	10	21		U-465	FED.	43-047-31985
NBU #147	NWSW	4	10	22		U-01191	FED.	43-047-31984
NBU #148	SESW	4	10	22		U-01191	FED.	43-047-31983
NBU #149	NESE	5	10	22		U-01191	FED.	43-047-31982
NBU #150	SENW	9	10	22		U-01196-B	FED.	43-047-31992
NBU #151	NWNW	9	10	22		U-01196-B	FED.	43-047-31991
NBU #152	SESE	9	10	22		U-01196-D	FED.	43-047-31990
NBU #153	SWNW	11	10	22		ST U-01197-A	STATE	43-047-31975
NBU #154	NWSE	26	9	21		ST ML-22934	STATE	43-047-32003
NBU #155	SENW	31	9	22		ST ML-23607	STATE	43-047-32004
NBU #156	SWNW	35	9	21		ST U-01194	STATE	43-047-32005
NBU #157	SESW	32	9	22		ST ML-22649	STATE	43-047-32007
NBU #158	NWSE	27	9	21		ST U-01194-A	STATE	43-047-31997
NBU #159	NESW	35	9	21		ST U-01194	STATE	43-047-31996
NBU #160	SESW	31	9	22		ST ML-22935-A	STATE	43-047-32006
NBU #161	SESE	32	9	22		ST ML-22649	STATE	43-047-32023
NBU #162	SENW	12	10	20		U-4478	FED.	43-047-32066
NBU #163	NENW	14	10	21		U-465	FED.	43-047-32069
NBU #164	NWSE	3	10	22		U-01191-A	FED.	43-047-32055
NBU #165	NENW	3	10	22		U-01191	FED.	43-047-32057
NBU #166	SWSE	28	9	21		U-0576	FED.	43-047-32065
NBU #167	SESW	25	9	21		ST U-01194	STATE	43-047-32054
NBU #168	NWSW	12	10	20		U-4478	FED.	43-047-32117
NBU #169	SESW	12	10	20		U-4478	FED.	43-047-32118

13-Apr-92

NATURAL BUTTES

UINTAH COUNTY, UTAH

WELL #	LOCATION QUAD SEC TWP RGE	STATE OR BLM LEASE #	SURFACE	API NUMBER
NBU #170	NWNW 4 10 22	U-01191-A	FED.	43-047-32169
NBU #171	SENE 5 10 22	U-01191-A	FED.	43-047-32115
NBU #172	NENE 19 9 22	U-0284	UTE	43-047-32194
NBU #173	NWNE 33 9 22	U-01191-A	FED.	43-047-32116
NBU #174	NWNW 11 9 21	U-0141315	UTE	43-047-32193
NBU #175	NENW 28 9 21	U-0576	FED.	43-047-32143
NBU #176	SWNW 28 9 21	U-0576	FED.	43-047-32144
NBU #177	NESE 29 9 21	U-0581	FED.	43-047-32112
NBU #178	NWNE 30 9 21	U-0581	FED.	43-047-32121
NBU #179	SWSW 10 10 21	U-01416-A	FED.	43-047-32145
NBU #180	SWSE 10 10 22	U-025187	FED.	43-047-32113
NBU #181	SESW 9 9 21	U-0576	UTE	43-047-32161
NBU #182	SENW 11 9 21	U-0141315	UTE	43-047-32162
NBU #183 ✓	SWNW 27 9 21	ST U-01194-A	STATE	43-047-32122
NBU #184	SESW 30 9 22	U-463	FED.	43-047-32170
NBU #185	SWNE 3 10 22	U-01191-A	FED.	43-047-32171
NBU #186	SENE 30 9 22	U-463	FED.	43-047-
NBU #187	SESW 34 9 22	U-0149077	FED.	43-047-
NBU #188	SWSW 10 10 22	U-01196-C	FED.	43-047-
NBU #189	SESW 23 9 21	U-0149075	UTE	43-047-
NBU #190 ✓	NWNE 26 9 21	ST U-01194	STATE	43-047-
CIGE 110-7-9-21	SWSE 7 9 21	U-0575-B	UTE	43-047-31959
CIGE 111-13-9-21	SESW 13 9 21	U-01193	UTE	43-047-31954
CIGE 112-19-9-21	SESE 19 9 21	U-0581	UTE	43-047-31945
CIGE 113-21-9-21	SWNE 21 9 21	U-0576	UTE	43-047-31944
CIGE 114-34-9-21 ✓	NESE 34 9 21	ST U-01194-A	STATE	43-047-31915
CIGE 115-35-9-21 ✓	NWNE 35 9 21	ST ML-22582	STATE	43-047-31918
CIGE 116-29-9-22 ✓	NWSW 29 9 22	ST ML-22935	STATE	43-047-31919
CIGE 117-34-9-22	SWNW 34 9 22	U-0149077	FED.	43-047-31928
CIGE 118-35-9-22	NESE 35 9 22	U-010954A	FED.	43-047-32025
CIGE 119-15-10-21	NENE 15 10 21	U-01416-A	FED.	43-047-31927
CIGE 120-15-9-20	SENE 15 9 20	U-0144868	UTE	43-047-32032
CIGE 121-15-9-20	NWNE 15 9 20	U-0144868	UTE	43-047-32031
CIGE 122-7-9-21	NENE 7 9 21	U-0149767	UTE	43-047-32098
CIGE 123-7-9-21	SWNE 7 9 21	U-0575-B	UTE	43-047-32047
CIGE 124-9-9-21	NWSE 9 9 21	U-01188	UTE	43-047-32045
CIGE 125-13-9-21	NWNW 13 9 21	U-01193	UTE	43-047-32084
CIGE 126-13-9-21	NWSW 13 9 21	U-01193	UTE	43-047-32087
CIGE 127-16-9-21	NESW 16 9 21	ST ML-3141	UTE	43-047-32036
CIGE 128-18-9-21	NENE 18 9 21	U-0575	UTE	43-047-32046
CIGE 129-18-9-21	NENW 18 9 21	U-0581	UTE	43-047-32043
CIGE 130-19-9-21	NENE 19 9 21	U-0581	UTE	43-047-32030
CIGE 131-19-9-21	SWNE 19 9 21	U-0581	UTE	43-047-32029
CIGE 132-20-9-21	NWSW 20 9 21	U-0575	UTE	43-047-32028
CIGE 133-35-9-21 ✓	SWSE 35 9 21	ST ML-22582	STATE	43-047-31978
CIGE 134-1-10-20	SWSW 1 10 20	U-02270-A	FED.	43-047-31989
CIGE 135-3-10-21	SWSW 3 10 21	U-0149078	FED.	43-047-32001
CIGE 136-4-10-21 ✓	SWNE 4 10 21	ST ML-22940	STATE	43-047-31979
CIGE 137-6-10-21	SENE 6 10 21	U-01791	FED.	43-047-31988
CIGE 138A-6-10-21	SENW 6 10 21	U-01791	FED.	43-047-31987
CIGE 139-10-10-21	SWNE 10 10 21	U-0149079	FED.	43-047-31986
CIGE 140-16-10-21 ✓	NENE 16 10 21	ST ML-10755	STATE	43-047-31977
CIGE 141-7-10-22 ✓	NWNE 7 10 22	ST ML-23609	STATE	43-047-31970
CIGE 142-25-9-21 ✓	SENE 25 9 21	ST U-01189	STATE	43-047-31994
CIGE 143-34-9-21 ✓	SWNE 34 9 21	ST U-01194-A	STATE	43-047-31995
CIGE 144-2-10-22 ✓	SWNE 2 10 22	ST ML-22651	STATE	43-047-32022
CIGE 145-29-9-22 ✓	SENW 29 9 22	ST ML-22935	STATE	43-047-31993
CIGE 146-16-10-21 ✓	NWNE 16 10 21	ST ML-10755	STATE	43-047-32021
CIGE 147-36-9-22 ✓	SESW 36 9 22	ST ML-22650	STATE	43-047-32020
CIGE 148-31-9-22 ✓	NWNE 31 9 22	ST ML-22935-A	STATE	43-047-32024
CIGE 149-8-10-21	NWNE 8 10 21	U-01791	FED.	43-047-32056
CIGE 150-9-10-21	SWNE 9 10 21	U-01416	FED.	43-047-32058
CIGE 151-10-10-21	SWSE 10 10 21	U-0149079	FED.	43-047-32059
CIGE 152-33-9-22	SESW 33 9 22	U-01191-A	FED.	43-047-32068
CIGE 153-35-9-22	SESW 35 9 22	U-010954-A	FED.	43-047-32067
CIGE 154-13-10-20	NWNW 13 10 20	U-4485	STATE	43-047-32119
CIGE 155-9-9-21	SENE 9 9 21	U-01188-B	UTE	43-047-32157

13-Apr-92

NATURAL BUTTES

UINTAH COUNTY, UTAH

WELL #	LOCATION			RGE	STATE OR BLM		SURFACE	API NUMBER
	QUAD	SEC	TWP		LEASE #			
CIGE 156-16-9-21	NESE	16	9	21	ST ML-3282	UTE	43-047-32195	
CIGE 157-16-9-21	SWNW	16	9	21	U-38409	UTE	43-047-32160	
CIGE 158-21-9-21	NESE	21	9	21	U-0576	UTE	43-047-32158	
CIGE 159-6-10-21	NWNE	6	10	21	U-01791	FED.	43-047-32120	
CIGE 160-14-10-21	SWSE	14	10	21	U-01393-C	FED.	43-047-32124	
CIGE 161-2-10-22	SESE	2	10	22	ST ML-22651	STATE	43-047-32168	
CIGE 162-36-9-22	SESE	36	9	22	ST ML-22650	STATE	43-047-32164	
CIGE 163-15-9-21	SENE	15	9	21	U-01193	UTE	43-047-32192	
CIGE 164-34-9-22	NWNE	34	9	22	U-0149077	FED.	43-047-32141	
CIGE 165-1-10-20	SWNW	1	10	20	U-02270-A	FED.	43-047-32114	
CIGE 166-3-10-21	NENW	3	10	21	U-0149078	FED.	43-047-32172	
CIGE 167-7-10-21	NENE	7	10	21	U-01791	FED.	43-047-32142	
CIGE 168-16-10-21	NWSE	16	10	21	ST ML-10755	STATE	43-047-32123	
CIGE 169-2-10-21	SENW	2	10	21	ST ML-22652	STATE	43-047-	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Designation and Serial No. UTU-4478
2. Name of Operator Coastal Oil & Gas Corporation		6. If Indian, Allottee or Tribe Name N/A
3. Address and Telephone No. P.O. Box 749 Denver, CO 80201-0749 (303) 573-4476		7. If Unit or CA, Agreement Designation Natural Buttes Unit
4. Location of Well (Fontage, Sec., T., R., M., or Survey Description) 1980' FNL & 1800' FWL (SE/NW) Section 12, T10S, R20E		8. Well Name and No. NBU #162
		9. API Well No. 43-047-32066
		10. Field and Pool, or Exploratory Area Natural Buttes
		11. County or Parish, State Uintah County, Utah

CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other Frac Stimulation
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Please see the attached chronological history for the fracture stimulation procedure performed on the above-referenced well.

RECEIVED

SEP 09 1992

DIVISION OF
OIL GAS & MINING

4. I hereby certify that the foregoing is true and correct.

Signed [Signature] Title Regulatory Analyst Date 9/2/92

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any: _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side

THE COASTAL CORPORATION
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

PAGE 2

NBU #162
SE/NW SECTION 12, T10S, R20E
NATURAL BUTTES UNIT
UINTAH COUNTY, UTAH
WI: 60.000% COGC AFE: 13174
TD: 6200' SD: 11/3/91
CSG: 5-1/2" @ 6198'
PERFS: 5113'-5925' (WASATCH)
CWC(M\$): \$358.8

11/16/91 MIRU Welltech #247.
DC: \$21,220 TC: \$200,550

11/17/91 Prep to run CBL. Finish MIRU CU. TIH w/4-3/4" mill & 195 jts 2-3/8" tbq. Tag PBD @ 6071'. Circ hole w/150 bbls 3% KCl wtr. POOH w/tbg.
DC: \$2,560 TC: \$203,110

11/18/91 Prep to swab. MIRU wireline company. Ran CBL-GR from PBD to surface. TOC @ 150'. PT csg to 5000 psi. Perf Wasatch w/11 holes from 5113' to 5925'. RIH w/2-3/8" tbq. Landed @ 5071'. ND BOP, NU WH. RU Smith Energy. Breakdown perfs w/4000 gals 3% KCl wtr w/22 ball sealers. AIR 6.3 BPM @ 4700 psi. Balled off perfs. Surged off balls and finish job. ISIP 1210 psi, 15 min 780 psi. RD Smith. Flow back well.
DC: \$9,780 TC: \$212,890

11/19/91 Prep to swab. SICP 200 psi, SITP 200 psi. Blew down in one minute. Made 21 swab runs, rec 122 BLW. IFL @ sfc, FFL @ 4500'. Well did not kick off.
DC: \$1,920 TC: \$214,810

11/20/91 Flow tstg well. SICP 1500 psi, SITP 1500 psi. Well kicked off. Unloaded 20 BW in 1 hr. Start flow tstg on 20/64" chk at 2:00 p.m. flwg 200 MCFD, FTP 100 psi, SICP 450 psi, 20/64" chk, 1-1/2 BWPH.
DC: \$870 TC: \$215,680

11/21/91 Flwg 300 MCFD, FTP 100 psi, CP 400 psi, 20/64" chk, dry gas.

11/22/91 SI, waiting on frac. Flwg 300 MCFD, FTP 100 psi, CP 400 psi, 20/64" chk. Killed well. TOH w/tbg. LD tbq. ND BOP, NU WH. RDMO CU. Drop from report until further activity.
DC: \$1,390 TC: \$217,070

8/12/92 WO frac. MIRU Well Tech rig #298. Kill well w/100 bbls 3% KCl. PU & RIH w/blast sub, 163 jts, PSN, 1-jt & NU. EOT @ 5063'. ND BOP, NU tree. SDFN.
DC: \$20,000 TC: \$237,070

8/13/92 WO frac. RD & MO Well Tech rig #298. Drop from report until further activity.
DC: \$200 TC: \$237,270

8/18/92 Cleanup after frac. Haul to location & spot wtr, CO₂ and sand. RU Smith Energy & frac Wasatch perfs 5113'-5925' w/280,000# 20/40 sand w/1735 bbls CMHPG gel & 145 tons CO₂. AIR 30 BPM @ 3750 psi, max 4000 psi. ISIP 2210 psi, 5 min 2200 psi, 10 min 2190 psi, 15 min 2170 psi.
DC: \$83,850 TC: \$321,120

8/19/92 Flwg 1.5 MMCFD CO₂, FTP 975 psi, CP 900 psi, 18/64" chk, 15-20 BWPD.

8/20/92 Flwg 1.2 MMCFD, FTP 900 psi, CP 800 psi, 18/64" chk, 15 BWPD.

8/21/92 Well SI. Flwg 1.5 MMCFD, FTP 825 psi, CP 750 psi, 18/64" chk, dry gas. SI @ 6:00 a.m. Drop from report.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.

UTU-4478

6. If Indian, Allottee or Tribe Name

N/A

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone No.

P.O. Box 749 Denver, CO 80201-0749 (303) 573-4476

4. Location of Well (Fontage, Sec., T., R., M., or Survey Description)

1980' FNL & 1800' FWL (SE/NW)
Section 12, T10S, R20E

7. If Unit or CA, Agreement Designation

Natural Buttes Unit

8. Well Name and No.

NBU #162

9. API Well No.

43-047-32066

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah County, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment

☐ Recompletion

☐ Plugging Back

☐ Casing Repair

☐ Altering Casing

☒ Other First Sales

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut-Off

☐ Conversion to Injection

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The above-referenced well was connected to CIG's gas salesline and first sales occurred at 11:30 AM, 8/31/92 w/a rate of 1279 MCFPD, 0 BOPD, 0 BWP, FTP 1936, SICP 1602 and 10/64" choke.

RECEIVED

OCT 02 1992

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed [Signature] Title Regulatory Analyst

Date 9/29/92

(This space for Federal or State office use)

Approved by _____
Conditions of approval, if any:

Title _____

Date _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make in any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☐ OTHER _____

2. NAME OF OPERATOR:
El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR: 8 South 1200 East CITY Vernal STATE Utah ZIP 84078 PHONE NUMBER: 435-789-4433

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

COUNTY:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☐ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☒ OTHER: Name Change

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.

See Exhibit "A"

Bond # 400JU0708

Coastal Oil & Gas Corporation

NAME (PLEASE PRINT) John T. Elzner

TITLE Vice President

SIGNATURE

DATE 06-15-01

El Paso Production Oil & Gas Company

NAME (PLEASE PRINT) John T. Elzner

TITLE Vice President

SIGNATURE

DATE 06-15-01

(This space for State use only)

RECEIVED

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING

State of Delaware
Office of the Secretary of State

PAGE 1

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

MAR 9 2001

DIVISION OF
OIL, GAS AND MINING



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

0610204 8100

AUTHENTICATION: 1061007

010162788

DATE: 04-03-01

CERTIFICATE OF AMENDMENT

OF

CERTIFICATE OF INCORPORATION

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST." so that, as amended, said Article shall be and read as follows:


"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL & GAS CORPORATION


David L. Siddall
Vice President

Attest:


(Margaret E. Roark, Assistant Secretary)

RECEIVED

STATE OF DELAWARE
SECRETARY OF STATE
DIVISION OF CORPORATIONS
FILED 11:00 AM 03/09/2001
010118394 - 0610204

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

RECEIVED

JUL 12 2001

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:

3106

UTSL-065841

(UT-924)

JUL 10 2001

NOTICE

El Paso Production Oil & Gas Company : Oil and Gas
Nine Greenway Plaza :
Houston TX 77046-0095 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Coastal Oil & Gas Corporation into El Paso Production Oil & Gas Company with El Paso Production Oil & Gas Company being the surviving entity.

For our purposes, the name change is recognized effective March 9, 2001.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Coastal Oil & Gas Corporation to El Paso Production Oil & Gas Company. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Wyoming and Colorado.



Opolonia L. Abeyta
Acting Chief, Branch of
Minerals Adjudication

Enclosure

1. Exhibit of Leases (1 pp)

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
~~State of Utah, DOGM,~~ Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

Exhibit of Leases

UTUSL-065841A	UTU-47172	UTU-74415	UTU-53860
UTU-28652	UTU-50687	UTU-74416	UTU-66401
UTU-37943	UTU-52298	UTU-75091	UTU-67868
UTU-44089	UTU-0109054	UTU-75096	UTU-65389
UTU-44090A	UTU-0143511	UTU-75097	UTU-77084
UTU-61263	UTU-0143512	UTU-75673	UTU-61430
UTU-00343	UTU-38401	UTU-76259	UTU-72633
UTU-02651	UTU-38411	UTU-76260	UTU-72650
UTU-02651B	UTU-38418	UTU-76261	UTU-49692
UTU-0142175	UTU-38419	UTU-76493	UTU-57894
UTU-70235	UTU-38420	UTU-76495	UTU-76829
UTU-70406	UTU-38421	UTU-76503	UTU-76830
UTU-74954	UTU-38423	UTU-78228	UTU-76831
UTU-75132	UTU-38424	UTU-78714	
UTU-75699	UTU-38425	UTU-78727	
UTU-76242	UTU-38426	UTU-78734	
UTU-78032	UTU-38427	UTU-79012	
UTU-4377	UTU-38428	UTU-79011	
UTU-4378	UTU-53861	UTU-71694	
UTU-7386	UTU-58097	UTU-00576	
UTU-8344A	UTU-64376	UTU-00647	
UTU-8345	UTU-65222	UTU-01470D	
UTU-8347	UTU-65223	UTU-0136484	
UTU-8621	UTU-66746	UTU-8344	
UTU-14646	UTU-67178	UTU-8346	
UTU-15855	UTU-67549	UTU-8648	
UTU-25880	UTU-72028	UTU-28212	
UTU-28213	UTU-72632	UTU-30289	
UTU-29535	UTU-73009	UTU-31260	
UTU-29797	UTU-73010	UTU-33433	
UTU-31736	UTU-73013	UTU-34711	
UTU-34350	UTU-73175	UTU-46699	
UTU-34705	UTU-73434	UTU-78852	
UTU-37116	UTU-73435	UTU-78853	
UTU-37355	UTU-73444	UTU-78854	
UTU-37573	UTU-73450	UTU-075939	
UTU-38261	UTU-73900	UTU-0149767	
UTU-39223	UTU-74409	UTU-2078	
UTU-40729	UTU-74410	UTU-44426	
UTU-40736	UTU-74413	UTU-49530	
UTU-42469	UTU-74414	UTU-51026	

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH		4-KAS
2. CDW	✓	5-LP ✓
3. JLT		6-FILE

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

X Merger

The operator of the well(s) listed below has changed, effective: **3-09-2001****FROM:** (Old Operator):

COASTAL OIL & GAS CORPORATION

Address: 9 GREENWAY PLAZA STE 2721

HOUSTON, TX 77046-0995

Phone: 1-(713)-418-4635

Account N0230

TO: (New Operator):

EL PASO PRODUCTION OIL & GAS COMPANY

Address: 9 GREENWAY PLAZA STE 2721 RM 2975B

HOUSTON, TX 77046-0995

Phone: 1-(832)-676-4721

Account N1845

CA No.

Unit: NATURAL BUTTES

WELL(S)

NAME	API NO	ENTITY NO	SEC TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 342-35E	43-047-32212	2900	35-09S-22E	FEDERAL	GW	P
CIGE 186-35-9-22	43-047-32590	2900	35-09S-22E	FEDERAL	GW	TA
CIGE 193-35-9-22	43-047-32973	2900	35-09S-22E	FEDERAL	GW	P
NBU CIGE 35-1-10-20	43-047-30494	2900	01-10S-20E	FEDERAL	GW	P
CIGE 134-1-10-20	43-047-31989	2900	01-10S-20E	FEDERAL	GW	P
CIGE 165-1-10-20	43-047-32114	2900	01-10S-20E	FEDERAL	GW	P
CIGE 177-1-10-20	43-047-32322	2900	01-10S-20E	FEDERAL	GW	P
NBU 358-1E	43-047-32388	2900	01-10S-20E	FEDERAL	GW	P
CIGE 229-1-10-20	43-047-33006	2900	01-10S-20E	FEDERAL	GW	P
NBU 497-1E	43-047-33123	2900	01-10S-20E	FEDERAL	GW	P
NBU 63-12B	43-047-30466	2900	12-10S-20E	FEDERAL	GW	P
NBU 72N-3	43-047-31088	2900	12-10S-20E	FEDERAL	GW	P
NBU 162	43-047-32066	2900	12-10S-20E	FEDERAL	GW	P
NBU 168	43-047-32117	2900	12-10S-20E	FEDERAL	GW	P
NBU 169	43-047-32118	2900	12-10S-20E	FEDERAL	GW	P
NBU 295	43-047-32939	2900	12-10S-20E	FEDERAL	GW	P
NBU 523-12E	43-047-33685	2900	12-10S-20E	FEDERAL	GW	P
NBU 516-12E	43-047-33696	2900	12-10S-20E	FEDERAL	GW	P
NBU 524-12E	43-047-33701	2900	12-10S-20E	FEDERAL	GW	P
NBU 26-13B	43-047-30364	2900	13-10S-20E	FEDERAL	GW	P

OPERATOR CHANGES DOCUMENTATION

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/19/2001
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/19/2001
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 06/21/2001
4. Is the new operator registered in the State of Utah: YES Business Number: 608186-0143

5. If **NO**, the operator was contacted contacted on: N/A
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 07/10/2001
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 07/10/2001
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: 07/10/2001
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 08/01/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 08/01/2001
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE BOND VERIFICATION:

1. State well(s) covered by Bond No.: N/A

FEDERAL BOND VERIFICATION:

1. Federal well(s) covered by Bond No.: WY 2793

FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond No: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

FILMING:

1. All attachments to this form have been **MICROFILMED** on: _____

FILING:

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filled in each well file on: _____

COMMENTS: Master list of all wells involved in operator change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company shall be retained in the "Operator Change File".

JAN. 17. 2003 3:34PM

STPORT

NO. 173 P. 2



WESTPORT OIL AND GAS COMPANY, L.P.

410 Seventeenth Street #2300 Denver Colorado 80202-4436
Telephone: 303 573 5404 Fax: 303 573 5609

February 1, 2002

Department of the Interior
Bureau of Land Management
2850 Youngfield Street
Lakewood, CO 80215-7093
Attention: Ms. Martha Maxwell

RE: BLM Bond CO-1203
BLM Nationwide Bond 158626364
Surety - Continental Casualty Company
Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.
Assumption Rider - Westport Oil and Gas Company, L.P.

Dear Ms. Maxwell:

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,
Westport Oil and Gas Company, L.P.

Debby J. Black
Debby J. Black
Engineer Technician

Encl:



United States Department of the Interior **RECEIVED**

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:

3106

UTU-25566 et al

(UT-924)

FEB 21 2002

NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas
410 Seventeenth Street, #2300 :
Denver Colorado 80215-7093 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405
UTU-20895
UTU-25566
UTU-43156
UTU-49518
UTU-49519
UTU-49522
UTU-49523



Robert Lopez
Chief, Branch of
Minerals Adjudication

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

UNITED STATES GOVERNMENT

memorandum

Branch of Real Estate Services
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to:
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for *Change of Operator*. You will be modifying your records to reflect *Change of Operator* once you have received all necessary documentation from the companies involved, and perhaps in advance of our *Notice of Concurrence/Approval of Change of Operator* where Indian leases are involved.


We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.

CC: Minerals & Mining Section of RES
Ute Energy & Mineral Resources Department: Executive Director
chrono





United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Washington, D.C. 20240

FEB 10 2003IN REPLY REFER TO:
Real Estate Services

Carroll A. Wilson
Principal Landman
Westport Oil and Gas Company, L.P.
1368 South 1200 East
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

A handwritten signature in black ink, reading "Perry E. Brown", is positioned above the title of the Director.

Director, Office of Trust Responsibilities

ACTING

Enclosure



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

IN REPLY REFER TO
UT-922

February 27, 2003

Westport Oil and Gas Company, L.P.
Attn: Gary D. Williamson
1670 Broadway, Suite 2800
Denver, Colorado 80202

Re: Natural Buttes Unit
Uintah County, Utah

Gentlemen:

On February 27, 2003, we received an indenture dated December 17, 2002, whereby El Paso Production Oil & Gas Company resigned as Unit Operator and Westport Oil and Gas Company, L.P., was designated as Successor Unit Operator for the Natural Buttes Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective February 27, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Natural Buttes Unit Agreement.

Your nationwide (Colorado) oil and gas bond No. 1203 will be used to cover all operations within the Natural Buttes Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)
SITLA
Division of Oil, Gas & Mining
Minerals Adjudication Group
File - Natural Buttes Unit (w/enclosure)
Agr. Sec. Chron
Fluid Chron

UT922:TAThompson:tt:02/27/2003

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

9 Greenway Plaza

Houston

STATE TX

ZIP 77064-0995

PHONE NUMBER:

(832) 676-5933

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE	
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND # _____

State Surety Bond No. RLB0005236

Fee Bond No. RLB0005238

EL PASO PRODUCTION OIL & GAS COMPANY

By: _____

Jon R. Nelsen, Attorney-in-Fact

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.

NAME (PLEASE PRINT)

David R. Dix

TITLE

Agent and Attorney-in-Fact

SIGNATURE

DATE

12/17/02

(This space for State use only)

Form 3160-5
(August 1999)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED EXHIBIT "A"

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

SEE ATTACHED EXHIBIT "A"

9. API Well No.

SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	SUCCESSOR OF
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompletes horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zone. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed when testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF, BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Date

March 4, 2003

DIV. OF OIL, GAS & MINING

Approved by

THIS SPACE FOR FEDERAL OR STATE USE

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW ✓

3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: 12-17-02

FROM: (Old Operator):	TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY	WESTPORT OIL & GAS COMPANY LP
Address: 9 GREENWAY PLAZA	Address: P O BOX 1148
HOUSTON, TX 77064-0995	VERNAL, UT 84078
Phone: 1-(832)-676-5933	Phone: 1-(435)-781-7023
Account No. N1845	Account No. N2115

CA No.

Unit:

NATURAL BUTTES

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
NBU CIGE 62D-32-9-22	36-09S-22E	43-047-30885	2900	STATE	GW	P
NBU 213-36J	36-09S-22E	43-047-31268	2900	STATE	GW	P
NBU 318-36E	36-09S-22E	43-047-32204	2900	STATE	GW	P
NBU 343-36E	36-09S-22E	43-047-32205	2900	STATE	GW	P
CIGE 221-36-9-22	36-09S-22E	43-047-32868	2900	STATE	GW	P
CIGE 222-36-9-22	36-09S-22E	43-047-32869	2900	STATE	GW	P
CIGE 147-36-9-22	36-09S-22E	43-047-32020	2900	STATE	GW	PA
CIGE 177-1-10-20	01-10S-20E	43-047-32322	2900	FEDERAL	GW	P
NBU CIGE 35-1-10-20	01-10S-20E	43-047-30494	2900	FEDERAL	GW	S
CIGE 134-1-10-20	01-10S-20E	43-047-31989	2900	FEDERAL	GW	P
CIGE 165-1-10-20	01-10S-20E	43-047-32114	2900	FEDERAL	GW	P
NBU 358-1E	01-10S-20E	43-047-32388	2900	FEDERAL	GW	P
CIGE 229-1-10-20	01-10S-20E	43-047-33006	2900	FEDERAL	GW	P
NBU 497-1E	01-10S-20E	43-047-33123	2900	FEDERAL	GW	P
NBU 162	12-10S-20E	43-047-32066	2900	FEDERAL	GW	P
NBU 63-12B	12-10S-20E	43-047-30466	2900	FEDERAL	GW	P
NBU 72N-3	12-10S-20E	43-047-31088	2900	FEDERAL	GW	P
NBU 168	12-10S-20E	43-047-32117	2900	FEDERAL	GW	P
NBU 169	12-10S-20E	43-047-32118	2900	FEDERAL	GW	P
NBU 295	12-10S-20E	43-047-32939	2900	FEDERAL	GW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
5. If **NO**, the operator was contacted on: _____

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 03/19/2003
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 03/19/2003
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: RLB 0005236

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 158626364

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: RLB 0005239

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The NEW operator of any fee well(s) listed covered by Bond Number RLB 0005238
2. The FORMER operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The FORMER operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Multiple Wells - see attached

5. Lease Serial No.

Multiple Wells - see attached

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

891008900A

8. Well Name and No.

Multiple Wells - see attached

9. API Well No.

Multiple Wells - see attached

10. Field and Pool, or Exploratory Area

Natural Buttes Unit

11. County or Parish, State

Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Westport Oil & Gas requests a variance to Onshore Order No. 4, Part IIIC.a. requiring each sales tank be equipped with a pressure-vacuum thief hatch and/or vent line valve. The variance is requested as an economic analysis shows the value of the shrunk condensate will not payout the incremental cost of purchasing and maintaining the valve resulting in a loss of value over the producing life of the well.

The volume lost to shrinkage by dropping the tank pressure from 6 ozs. to 0 psig is shown to be 0.3% of the tank volume. This was determined by lab analysis of a representative sample from the field. The sample shrunk from 98.82% of original volume to 98.52% when the pressure was dropped.

The average NBU well produces approximately 6 bbls condensate per month. The resulting shrinkage would amount to 0.56 bbls per month lost volume due to shrinkage. The value of the shrunk and lost condensate does not recoup or payout the cost of installing and maintaining the valves and other devices that hold the positive tank pressure. An economic run based on the loss and costs is attached.

Westport Oil & gas requests approval of this variance in order to increase the value of the well to the operator and the mineral royalty owners.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

J.T. Conley

Signature

COPY SENT TO OPERATOR

Date:

Initials:

Title

Date

Operations Manager

9-2-2003

SEP 10 2003

DIV. OF OIL, GAS, AND MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Federal Approval Of This Action Is Necessary

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Date: 9/16/03

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Westport Oil & Gas, L.P.

Project Economics Worksheet

Instructions:

Fill in blue boxes with before and after project data. The evaluation results are shown below and graphed automatically at the bottom of the page. This sheet is protected to prevent accidental alteration of the formulas. See JTC for changes. OPX entered as annual costs and/or as unit OPX costs for \$/BF and \$/MCF

Project Name:

Condensate Shrinkage Economics

Is this job a well pull or production rig job ??? ☒ N (Y or N)

	BEFORE \$/Year	AFTER \$/Year	DIFFERENCE \$/Year
Gross Oil Revenue	\$1,088	\$1,099	\$11
Gross Gas Revenue	\$0	\$0	\$0
NGL Revenue	\$0	\$0	\$0
PULING UNIT SERVICE			\$0
WIRELINE SERVICE			\$0
SUBSURF EQUIP REPAIRS			\$0
COMPANY LABOR			\$0
CONTRACT LABOR	\$0	\$200	\$200
CONTR SERVICE			\$0
LEASE FUEL GAS	\$0	\$0	\$0
UTILITIES - ELECTRICITY	\$0	\$0	\$0
CHEMICAL TREATING			\$0
MATERIAL & SUPPLY	\$0	\$150	\$150
WATER & HAULING			\$0
ADMINISTRATIVE COSTS			\$0
GAS PLANT PROCESSING			\$0
Totals	\$0	\$350	\$350

Increased OPX Per Year

Investment Breakdown:

	Cap/Exp Code	Cost, \$
Capital \$	820/830/840	\$1,200
Expense \$	830/860	\$0
Total \$		\$1,200

Oil Price	\$ 23.00	\$/BO
Gas Price	\$ 3.10	\$/MCF
Electric Cost	\$ -	\$/ HP / day
OPX/BF	\$ 2.00	\$/BF
OPX/MCF	\$ 0.62	\$/MCF

Production & OPX Detail:

	Before	After	Difference
Oil Production	0.192 BOPD	0.194 BOPD	0.002 BOPD
Gas Production	0 MCFPD	0 MCFPD	0 MCFPD
Wtr Production	0 BWPD	0 BWPD	0 BWPD
Horse Power	0 HP	0 HP	0 HP
Fuel Gas Burned	0 MCFPD	0 MCFPD	0 MCFPD

Project Life:

Life = 20.0 Years
(Life no longer than 20 years)

Internal Rate of Return:

After Tax IROR = #DIV/0!

AT Cum Cashflow:

Operating Cashflow = (\$2,917) (Discounted @ 10%)

Payout Calculation:

$$\text{Payout} = \frac{\text{Total Investment}}{\text{Sum(OPX + Incremental Revenue)}} = 1$$

Payout occurs when total AT cashflow equals investment
See graph below, note years when cashflow reaches zero

Payout = NEVER Years or #VALUE! Days


Gross Reserves:

Oil Reserves = 6 BO
Gas Reserves = 0 MCF
Gas Equiv Reserves = 38 MCFE

Notes/Assumptions:

An average NBU well produces 0.192 Bopd with no tank pressure. The production is increased to 0.194 Bopd if 4 ozs of pressure are placed on the tank. The increased production does not payout the valve cost or the estimated annual maintenance costs.

Project: Condensate Shrinkage Economics



Westport Oil and Gas, Inc.

NBU/Ouray Field

RFL 2003-022

COMPARISON OF FLASH BACK PRESSURES

Calculated by Characterized Equation-of-State

Flash Conditions		Gas/Oil Ratio (scf/STbbl) (A)	Specific Gravity of Flashed Gas (Air=1.000)	Separator Volume Factor (B)	Separator Volume Percent (C)
psig	°F				

Calculated at Laboratory Flash Conditions

80	70			1.019	
0	122	30.4	0.993	1.033	101.37%
0	60	0.0	—	1.000	98.14%

Calculated Flash with Backpressure using Tuned EOS

80	70			1.015	
6.0 oz	65	24.6	0.777	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
4.0 oz	65	24.7	0.778	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
2.0 oz	65	24.7	0.779	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
0	65	24.8	0.780	1.003	98.82%
0	60	0.0	—	1.000	98.52%

(A) Cubic Feet of gas at 14.696 psia and 60 °F per Barrel of Stock Tank Oil at 60 °F.

(B) Barrels of oil at indicated pressure and temperature per Barrel of Stock Tank Oil at 60 °F.

(C) Oil volume at indicated pressure and temperature as a percentage of original saturated oil volume.

Note: Bubblepoint of sample in original sample container was 80 psig at 70° F with 1 cc water

WELL	LEGALS	STFLEASENO	CANUMBER	APINO
NBU 149	5-10-22 NESE	UTU01191	891008900A	430473198200S1
NBU 150	9-10-22 SENW	UTU01196B	891008900A	430473199200S1
NBU 151	9-10-22 NWNW	UTU01196B	891008900A	430473199100S1
NBU 152	9-10-22 SESE	UTU01196D	891008900A	430473199000S1
NBU 153	11-10-22 SWNW	U01197A	891008900A	430473197500S1
NBU 154	26-9-21 NWSE	ML22934	891008900A	430473200300S1 ✓
NBU 155	31-9-22 SENW	ML23607	891008900A	430473200400S1 ✓
NBU 156	35-9-21 SWNW	U01194	891008900A	430473200500S1 ✓
NBU 157	32-9-22 SESW	ML22649	891008900A	430473200700S1 ✓
NBU 158	27-9-21 NWSE	U01194A	891008900A	430473199700S1 ✓
NBU 159SWD	35-9-21 NESW	U01194	891008900A	430473199600S1 ✓
NBU 161	32-9-22 SESE	ML22649	891008900A	430473202300S1 ✓
NBU 162	12-10-20 SENW	UTU4478	891008900A	430473206600S1
NBU 163	14-10-21 NENW	UTU465	891008900A	430473206900S1
NBU 164	3-10-22 NWSE	UTU01191A	891008900A	430473205500S1
NBU 165	3-10-22 NENW	UTU01191	891008900A	430473205700S1
NBU 166	28-9-21 SWSE	U05676	891008900A	430473206500S1
NBU 167	25-9-21 SESW	U01194	891008900A	430473205400S1 ✓
NBU 168	12-10-20 NWSW	UTU4478	891008900A	430473211700S1 ✓
NBU 169	12-10-20 SESW	UTU4478	891008900A	430473211800S1
NBU 170	4-10-22 NWNW	UTU01191A	891008900A	430473216900S1
NBU 171	5-10-22 SENE	UTU01191A	891008900A	430473211500S1
NBU 172	19-9-22 NENE	UTU0284	891008900A	430473219400S1
NBU 173	33-9-22 NWNE	UTU01191A	891008900A	430473211600S1
NBU 174	11-9-21 NWNW	UTU0141315	891008900A	430473219300S1
NBU 175	28-9-21 NENW	U05676	891008900A	430473214300S1
NBU 176	28-9-21 SWNW	U05676	891008900A	430473214400S1
NBU 177	29-9-21 NESE	UTU0581	891008900A	430473211200S1
NBU 178	30-9-21 NWNE	UTU0581	891008900A	430473212100S1
NBU 180	10-10-22 SWSE	UTU025187	891008900A	430473211300S1
NBU 181	9-9-21 SESW	UTU0576	891008900A	430473216100S1
NBU 182	11-9-21 SENW	UTU0141315	891008900A	430473216200S1
NBU 183	27-9-21 SWNW	U01194A	891008900A	430473212200S1 ✓
NBU 184	30-9-22 SESW	U463	891008900A	430473217000S1
NBU 185	3-10-22 SWNE	UTU01191A	891008900A	430473217100S1
NBU 186	30-9-22 SENE	U463	891008900A	430473223300S1
NBU 187	34-9-22 SESW	UTU0149077	891008900A	430473223000S1
NBU 188	10-10-22 SWSW	U01196C	891008900A	430473223400S1
NBU 189	23-9-21 SESW	UTU0149075	891008900A	430473223600S1
NBU 190	26-9-21 NWNE	U01194	891008900A	430473223200S1
NBU 191	15-9-21 SWSW	UTU010950A	891008900A	430473229800S1
NBU 192	22-9-21 NENW	UTU0147566	891008900A	430473229900S1
NBU 193	22-9-21 SWSW	UTU010950A	891008900A	430473230000S1
NBU 194	22-9-21 NESW	UTU010950A	891008900A	430473229800S1
NBU 195	11-9-21 NWNE	UTU0141317	891008900A	430473235500S1
NBU 198	22-9-21 NWSE	UTU010950A	891008900A	430473235700S1
NBU 199	9-9-21 SWSW	UTU0576A	891008900A	430473233700S1
NBU 200	19-9-22 NESE	UTU0284	891008900A	430473235900S1
NBU 201	9-9-21 SWNW	UTU0449767	891008900A	430473236400S1
NBU 202	8-9-21 NENE	UTU0449767	891008900A	430473233800S1
NBU 204	9-10-22 NWNE	UTU01196D	891008900A	430473234200S1
NBU 206	10-10-22 SWNW	U01196C	891008900A	430473234100S1
NBU 207	10-10-22 NENW	UTU69129	891008900A	430473232900S1 ✓
NBU 208	4-10-22 SESE	UTU01191	891008900A	430473234300S1
NBU 209	3-10-22 SWSW	UTU01191	891008900A	430473234500S1
NBU 210	10-10-22 NESW	U01196C	891008900A	430473234000S1
NBU 211	1-10-21 NWSW	U02842B	891008900A	430473233900S1
NBU 212	24-10-20 NENW	UTU4485	891008900A	430473239900S1
NBU 213	15-10-22 NWNW	UTU025187	891008900A	430473240100S1
NBU 214	27-9-21 NWSW	U01194	891008900A	430473246600S1 ✓
NBU 215	12-10-21 NWNW	UTU01190	891008900A	430473247100S1
NBU 216	15-9-21 NESW	UTU010950A	891008900A	430473248700S1

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING	
1. DJJ	
2. CDW	

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:		1/6/2006					
FROM: (Old Operator): N2115-Westport Oil & Gas Co., LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024	TO: (New Operator): N2995-Kerr-McGee Oil & Gas Onshore, LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024						
CA No.	Unit:	NATURAL BUTTES UNIT					
WELL NAME	SEC TWN RNG	<table border="1" style="width:100%"> <tr> <td>API NO</td> <td>ENTITY NO</td> <td>LEASE TYPE</td> <td>WELL TYPE</td> <td>WELL STATUS</td> </tr> </table>	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS			

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- 4a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- 4b. If **NO**, the operator was contacted on: _____
- 5a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- 5b. Inspections of LA PA state/fee well sites complete on: n/a 3 LA wells & all PA wells transferred
- 5c. Reports current for Production/Disposition & Sundries on: ok
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
7. **Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
8. **Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 5/15/2006
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
3. Bond information entered in RBDMS on: 5/15/2006
4. Fee/State wells attached to bond in RBDMS on: 5/16/2006
5. Injection Projects to new operator in RBDMS on: _____
6. Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: CO1203
2. Indian well(s) covered by Bond Number: RLB0005239
3. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
 The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

4. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006. KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

BLM BOND = C01203

BIA BOND = RLB0005237

APPROVED 5/16/06

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RANDY BAYNE

Signature

Randy Bayne

Title

DRILLING MANAGER

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY L.P.

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
MAY 10 2006

DIV OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

BRAD LANEY

Signature

Title

ENGINEERING SPECIALIST

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Brad Laney

Title

Date

5-9-06

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)



United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Colorado State Office
2850 Youngfield Street
Lakewood, Colorado 80215-7076

IN REPLY REFER TO:

CO922 (MM)
3106
COC017387 et. al.

March 23, 2006

NOTICE

Kerr-McGee Oil & Gas Onshore L.P. :
1999 Broadway, Suite 3700 : Oil & Gas
Denver, CO 80202 :

Merger/Name Change - Recognized

On February 28, 2006 this office received acceptable evidence of the following mergers and name conversion:

Kerr-McGee Oil & Gas Onshore L.P., a Delaware Limited Partnership, and Kerr-McGee Oil & Gas Onshore LLC, a Delaware Limited Partnership merger with and into Westport Oil and Gas Company L.P., a Delaware Limited Partnership, and subsequent Westport Oil & Gas Company L.P. name conversion to Kerr-McGee Oil & Gas Onshore L.P.

For our purposes the merger and name conversion was effective January 4, 2006, the date the Secretary of State of Delaware authenticated the mergers and name conversion.

Kerr-McGee Oil & Gas Onshore L.P. provided a list of oil and gas leases held by the merging parties with the request that the Bureau of Land Management change all their lease records from the named entities to the new entity, Kerr-McGee Oil & Gas Onshore L.P. In response to this request each state is asked to retrieve their own list of leases in the names of these entities from the Bureau of Land Management's (BLM) automated LR2000 data base.

The oil and gas lease files identified on the list provided by Kerr-McGee Oil & Gas Onshore L.P. have been updated as to the merger and name conversion. We have not abstracted the lease files to determine if the entities affected by the acceptance of these documents holds an interest in the lease, nor have we attempt to identify leases where the entity is the operator on the ground that maintains vested record title or operating rights interests. If additional documentation, for change of operator, is required you will be contacted directly by the appropriate Field Office. The Mineral Management Services (MMS) and other applicable BLM offices were notified of the merger with a copy of this notice

Please contact this office if you identify additional leases where the merging party maintains an interest, under our jurisdiction, and we will document the case files with a copy of this notice. If the leases are under the jurisdiction of another State Office that information will be forwarded to them for their action.

Three riders accompanied the merger/name conversion documents which will add Kerr-McGee Oil and Gas Onshore LLC as a principal to the 3 Kerr-McGee bonds maintained by the Wyoming State Office. These riders will be forward to them for their acceptance.

The Nationwide Oil & Gas Continental Casualty Company Bond #158626364 (BLM Bond #CO1203), maintained by the Colorado State Office, will remain in full force and effect until an assumption rider is accepted by the Wyoming State Office that conditions their Nationwide Safeco bond to accept all outstanding liability on the oil and gas leases attached to the Colorado bond.

If you have questions about this action you may call me at 303.239.3768.

/s/Martha L. Maxwell
Martha L. Maxwell
Land Law Examiner
Fluid Minerals Adjudication

Attachment:

List of OG Leases to each of the following offices:

MMS MRM, MS 357B-1

WY, UT, NM/OK/TX, MT/ND, WY State Offices

CO Field Offices

Wyoming State Office

Rider #1 to Bond WY2357

Rider #2 to Bond WY1865

Rider #3 to Bond WY1127



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>



IN REPLY REFER TO:
3106
(UT-922)

March 27, 2006

Memorandum

To: Vernal Field Office

From: Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the merger recognized by the Bureau of Land Management, Colorado State Office. We have updated our records to reflect the merger from Westport Oil and Gas Company L.P. into Kerr-McGee Onshore Oil and Gas Company. The merger was approved effective January 4, 2006.

Chief, Branch of
Fluid Minerals

Enclosure

Approval letter from BLM COSO (2 pp)

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare
Dave Mascarenas
Susan Bauman

RECEIVED

MAR 28 2006

BLM OF OIL, GAS & MINERALS

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-4478			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		8. WELL NAME and NUMBER: NBU 162			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		9. API NUMBER: 43047320660000			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1980 FNL 1800 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 20.0E Meridian: S		9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/24/2015 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, LP respectfully requests to plug and abandon the NBU 162 well. Please see the attached procedure for details. Thank you.					
<p style="color: red; font-weight: bold;">Approved by the Utah Division of Oil, Gas and Mining</p> <p>Date: <u>October 13, 2015</u></p> <p>By: <u></u></p> <p style="color: red; font-weight: bold; margin-top: 20px;">Please Review Attached Conditions of Approval</p>					
NAME (PLEASE PRINT) Kristina Geno		PHONE NUMBER 720 929-6824			
SIGNATURE N/A		TITLE Regulatory Analyst			
DATE 9/23/2015					



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047320660000

Plug # 2 should be a minimum of 200' in length and an additional 200' plug should be balanced across the top of the Green River formation from ~1500' to 1300' as required by Board Cause No. 190-5(b).

NBU 162

1980' FNL & 1800' FWL

SENE SEC. 12, T10S, R20E**Uintah County, UT**

KBE:	5053'	API NUMBER:	43-047-32066
GLE:	5065'	LEASE NUMBER:	UTU-4478
TD:	6200'	WI:	100.0000%
PBTD:	6071'	NRI:	83.490518 %

CASING: 12 1/4" hole
 8 5/8" 24# K-55 ST&C @ 256'
 Cemented w/ 150 sxs type V cement.

7.875" hole
 5 1/2" 17# J-55 LT&C @ 6,198'
 Cemented w/ 540 sxs Hyfill lead and 600 sxs type H 50-50 Poz tail. 70 bbls (±100 sxs cmt to pit). TOC @ ±186 by CBL.

TUBING: 2 3/8" 4.7 J-55 @ 5,928'.

Tubular/Borehole	Drift Inches	Collapse psi	Burst Psi	Capacities		
				Gal./ft.	Cuft/ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8,100	7,700	0.1624	0.0217	0.0039
5 1/2" 17# J-55	3.875	4,910	5,320	0.9764	0.1305	0.0232
8.625" 24# K-55	7.972	1,370	2,950	2.6749	0.3575	0.0636
Annular Capacities						
2.375" tbg. X 5.5" 17# csg				0.7463	0.0997	0.0178
5.5" csg X 7.875" borehole				1.2960	0.1733	0.0309
5.5" csg X 8 5/8" 24# csg				1.4407	0.1926	0.0343

GEOLOGIC INFORMATION:

Formation	Depth to top, ft.
Uinta	Surface
Mahogany	2146'
Parachute	3002'
Wasatch	4724'

SS- 144 Base of BMSW
BMSW Depth ~3000' KBE

PERFORATIONS:

Zone Name	Date	MD Top (ft)	MD Base (ft)	Shot Density (SPF)
Wasatch	11/10/1991	5113	5113	1
Wasatch	11/10/1991	5120	5120	1
Wasatch	11/10/1991	5126	5126	1
Wasatch	11/10/1991	5136	5136	1
Wasatch	11/10/1991	5641	5641	1
Wasatch	11/10/1991	5666	5666	1
Wasatch	11/10/1991	5672	5672	1
Wasatch	11/10/1991	5706	5706	1
Wasatch	11/10/1991	5908	5908	1
Wasatch	11/10/1991	5914	5914	1
Wasatch	11/10/1991	5925	5925	1

WELL HISTORY:

- 11/21/1991: - Perf and B/D Wasatch perms from 5113'-5925' with 4,000 gals of 3% KCl and ball sealers
- 8/18/1992: RIH w/ 163 jts tbg and set @ 5063'. Frac'd perms 5113' - 5925' w/ 280,000#'s of 20/40# sand, 1735 bbls gel, and 145 tons of CO₂.
- 1/15/2000: - C/O, acid & lower tubing workover; C/O from 5516' to 6071'. RIH w/ 2 3/8" 4.7 J-55 tbg and landed @ 5928'. Spot 24 bbls of 15% across all perms.
- 2/23/13: - Last slickline – Successful. Pulled spring and got a td @ 5,952'. Ran a 1.9" broach to SN. Tbg was clean.

NBU 162

PLUG & ABANDONMENT PROCEDURE

GENERAL

- H2S MAY BE PRESENT. CHECK FOR H2S AND TAKE APPROPRIATE PRECAUTIONS.
- CEMENT QUANTITIES BELOW ASSUME NEAT CLASS G, YIELD 1.145 CUFT./SX. IF A DIFFERENT PRODUCT IS USED, WELLSITE PERSONNEL ARE RESPONSIBLE FOR CORRECTING QUANTITIES TO YIELD THE STATED SLURRY VOLUME. WHEN SQUEEZING, INCLUDE 10% EXCESS PER 1000' OF DEPTH.
- BRINE WITH A MINIMUM DENSITY OF AT LEAST 9 PPG MUST BE PLACED BETWEEN ALL PLUGS. 10 PPG IS ASSUMED IN THIS PROCEDURE.
- ALL DISPLACEMENT FLUID SHALL CONTAIN CORROSION INHIBITOR AND BIOCIDES. PREMIX 5 GALLONS PER 100 BBLs FLUID.
- NOTIFY BLM 24 HOURS BEFORE MOVING ON LOCATION.

P&A PROCEDURE

Note: An estimated 77 sxs Class "G" cement needed for procedure

GYRO IS NEEDED.

1. MIRU. KILL WELL AS NEEDED. ND WH, NU AND TEST BOPE. **NOTE: NEED A GYRO RUN ON THIS WELL.**
1. POOH W/ TBG & LAY DOWN. RU WIRELINE AND MAKE A GAUGE RING RUN TO CHECK FOR FILL.
2. **PLUG #1, ISOLATE PERFORATIONS (5113'):** TIH AND SET A CIBP @ 5068'. PUH 10'. CIRCULATE ENTIRE HOLE W/ TREATED FRESH WATER. PRESSURE TEST CASING. SET A 105' CEMENT BALANCED PLUG (12 SXS, 13.7 CUFT, 2.45 BBLs) ON TOP OF CIBP. **TOC @ ±4963'.**
3. **PLUG #2, PROTECT BASE OF PARACHUTE (~3002') & BMSW (3000'):** SET A BALANCED CEMENT PLUG FROM 3052' – 2895' (157' COVERAGE) WITH (18 SXS / 20.6 CUFT / 3.67 BBL).
4. **PLUG #3 PROTECT MAHOGANY (~2146'):** SET A BALANCED CEMENT PLUG FROM 2146' – 2041' (105' COVERAGE) WITH (12 SXS / 13.7 CUFT / 2.45 BBL).
5. **PLUG #4, FILL SURFACE CASING SHOE (256'):** SET A BALANCED CEMENT PLUG FROM 256' – 203' (53' COVERAGE) WITH (6 SXS / 6.9 CUFT / 1.22 BBL).
6. **PLUG #5, FILL SURFACE HOLE & ANNULUS:** POOH. PERF CASING @ 100' AND PUMP A MIN OF 29 SXS / 33.2 CUFT / 5.9 BBLs / OR SUFFICIENT VOLUME TO FILL 5 ½" CASING AND 5.5" X 8.625" ANNULUS F/ 100' TO SURFACE
7. CUT OFF WELLHEAD AND INSTALL MARKER PER GUIDELINES.
8. RDMO. TURN OVER TO OPERATIONS FOR SURFACE REHAB

RBM – 8/24/15

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-4478
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 162
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1980 FNL 1800 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047320660000
10. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		STATE: UTAH
TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 6/17/2016 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, LP has plugged and abandoned the NBU 162 well. Please see the attached operations summary report for details. Thank you		
NAME (PLEASE PRINT) Candice Barber		PHONE NUMBER 435 781-9749
SIGNATURE N/A		TITLE HSE Representative
DATE 6/21/2016		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY June 22, 2016

US ROCKIES REGION
Operation Summary Report

Well: NBU 162				Spud date: 11/3/1991					
Project: UTAH-UINTAH				Site: NBU 162			Rig name no.: MILES-GRAY 1/1		
Event: ABANDONMENT				Start date: 6/16/2016				End date: 6/17/2016	
Active datum: RKB @0.00usft (above Mean Sea Level)				UWI: NBU 162					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation	
6/16/2016	7:00 - 12:00	5.00	ABANDP					RDMO NBU 921-35N1CS. ROAD RIG TO LOCATION. MIRU. SICP & SITP = 1550#. BLOW DOWN WELL TO FLOWBACK TANK. CNTRL TBNG W/ 15BBLS TMAC. CNTRL CSNG W/ 20BBLS TMAC. NDWH (BOLTS BADLY RUSTED). UN-LAND TBNG TO MAKE SURE IT WAS NOT STUCK (GOOD). LAND TBNG BACK ON HANGER. FUNCTION TEST BOP. NUBOP. R/U FLOOR & TBNG EQUIP. UN-LAND TBNG. RMV HANGER	
	12:00 - 15:20	3.33						MIRU SCANNERS. POOH WHILE SCANNING 192JTS 2-3/8" J-55 TBNG. L/D ALL TBNG AS SINGLES. TBNG SCAN RESULTS AS FOLLOWS: Y-BND= 78JTS R-BND= 114JTS. RDMO SCANNERS.	
	15:20 - 18:30	3.17						P/U & RIH W/ 5-1/2" WEATHERFORD CIBP + 160JTS 2-3/8" J-55 Y-BND TBG. SET CIBP @ 5068'. PUH 10'. L/D 1JT TBNG. SWIFN. LOCK RAMS. SDFN.	
6/17/2016	7:00 - 7:15	0.25	ABANDP	48	B			SAFETY = JSA	

US ROCKIES REGION

Operation Summary Report

Well: NBU 162				Spud date: 11/3/1991				
Project: UTAH-UINTAH			Site: NBU 162				Rig name no.: MILES-GRAY 1/1	
Event: ABANDONMENT			Start date: 6/16/2016				End date: 6/17/2016	
Active datum: RKB @0.00usft (above Mean Sea Level)			UWI: NBU 162					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	7:15 - 15:30	8.25	ABANDP					SICP & SITP= 10#. CNTRL WELL. MIRU CMT CREW. BREAK CONV CIRC W/ TMAC. CIRC WELL BORE CLEAN W/ 120BBLS TOTAL TMAC. GLADE RICH W/ BLM ON LOCATION TO WITNESS P&A. PRESSURE TEST CSG & CIBP GOOD @ 500#. LOST 0# IN 15MIN. PUMP CMT PLUGS AS FOLLOWS: #1. CIBP @ 5068'. EOT @5058'. PUMP 2BBLS FRESH WATER LEAD. PUMP 15SX 15.8# G CMT. DISPLACE W/ 18.5BBLS TMAC. PUH TBG. CMT 5058'-4925' #2. EOT @3052'. PUMP 2BBLS FRESH WATER LEAD. PUMP 25SX 15.8# G CMT. DISPLACE W/ 10.4BBLS TMAC. PUH TBG. CMT 3052'-2832' #3 EOT @ 2146' . PUMP 2BBLS FRESH WATER LEAD. PUMP 15SX 15.8# G CMT. DISPLACE W/ 7.2BBLS TMAC. PUH TBG. CMT 2146'-2013'. #4 EOT @1500'. PUMP 2BBLS FRESH WATER LEAD. PUMP 25SX 15.8# G CMT. DISPLACE W/ 4.3 BBLS TMAC. PUH TBG. CMT 1500'-1280'. #5. EOT @ 256'. PUMP 2BBLS FRESH WATER LEAD. PUMP10SX 15.8# G CMT. DISPLACE W/ 1BBL TMAC. POOH ALL TBG. CMT 256'-168'. MIRU WIRELINE. PERF 5-1/2" CSG @ 100' W/ 4HOLE X 1' PERF GUN. POOH E-LINE.RDMO E-LINE. R/D FLOOR & TBG EQUIP. NDBOP. INSTALL TBG HANGER W/ BULL PLUG. #6. SURFACE CMT JOB. BREAK CONV CIRC W/ FRESH WATER. HAD RETURNS W/ 3BBLS. PUMP 50SX 15.8# G CMT DOWN 5-1/2" CSG & UP 9-5/8" SURFACE. CSG. FULL RETURNS @ SURFACE. RDMO WORKOVER RIG. MIRU ROUSTABOUT CREW. EXPOSE WELLHEAD. CUT & LOWER WELLHEAD. FULL OF CMT. INSTALL MARKER PLATE. BACKFILL WELLHEAD. WELLHEAD COORDINATES: LAT:39.964388 LONG: -109.616905